

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

JULY, 1952.



Vol. XLVII, No. 7

FORTY-SEVENTH YEAR OF PUBLICATION

PRICE 1s. 6d.

ANNUAL SUBSCRIPTION 18s., POST FREE. 33-00 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Aeronautics and Civil Engineering	193
Rectangular Slabs Spanning in Two Directions. <i>By Professor H. Craemer</i>	195
Book Reviews	202
The Pathology of Reinforced Concrete. <i>By Henry Lossier</i>	203
Analysis of Groups of Piles. <i>By R. J. Wilkins, M.Sc.(Eng.)</i>	209
A Precast Reinforced Concrete Dome	212
Concrete Piles in Holland. <i>By P. F. van der Meulen Bosma</i>	217
Four Reinforced Concrete Chimneys at Fawley, Hants	222
Pressure-type Air Meters for Air-entrained Concrete. <i>By P. J. F. Wright, B.Sc., and A. D. McCubbin</i>	225

No. 586.

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1



For over 60 years

this trade mark has stood for speed and
strength in reinforced concrete work.

DRAGON

(Brand)

PORTLAND CEMENT

Supplied by

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.
PENARTH, SOUTH WALES

Telephone : Penarth 300

Telegrams : "Cement, Penarth"

Burton's

TUBULAR STEEL TRENCH STRUTS


(ADJUSTABLE)



REGISTERED



TRADE MARK



OUTSTANDING ADVANTAGES

1.—Save at least 80% labour by eliminating the old-fashioned system of cutting, wedging and nailing timber strutting; no waste of timber.

2.—Fixed by one man in one minute.

3.—Being steel complete, they are practically everlasting and can be used over and over again indefinitely.

4.—Take up very little store space and very compact for transport.

5.—No loose parts which can be lost, so they are always ready for work.

IN THREE SIZES

Size No.	Length		Approx. Weight
	Closed	Expanded	
1.	1' 6"	2' 3"	14 lb.
2.	2' 4"	3' 6½"	19 lb.
3.	3' 4"	5' 6"	24 lb.

Burton's Patent Solid Dropforged Steel Scaffolding Fittings

THE LONDON & MIDLAND STEEL SCAFFOLDING CO., LTD.

ST. LUKE'S WORKS, OLD HILL, STAFFORDSHIRE


Telegrams: DUBELGRIP, CRADLEY HEATH.

Telephone: CRADLEY HEATH 6237/8

London Offices: BURWOOD HOUSE, CAXTON STREET, S.W.1

Telephone: Abbey 6483/4.

Telegrams: Dubelgrip, Sowest, London



FACTORY WORK IN COURSE OF CONSTRUCTION

YORKSHIRE HENNEBIQUE

FERRO - CONCRETE SPECIALISTS
SINCE 1904

HEAD OFFICE : VIADUCT WORKS, KIRKSTALL ROAD, LEEDS, 4

Telephone : Leeds 20687-8-9

Telegrams : Ferro, Leeds

BRANCH OFFICES : 30, WINCOLMLEE, HULL. Telephone : Hull 33501

SCOTLAND : ALNESS, ROSS-SHIRE. Telephone : Alness 289

Oil Refinery Construction at Coryton




4,200-TON reinforced concrete caisson in position at Coryton after its ten mile down river journey from Tilbury. This structure forms part of the water intake jetty for the new oil refinery at Coryton under construction for Vacuum Oil Company Limited in conjunction with the Lummus Company Limited.

LAING

Contractors for every class of Building and Civil Engineering at home and overseas

John Laing and Son Limited, London, Carlisle, Johannesburg, Lusaka. Established in 1848



**LEADING CONTRACTORS
EVERYWHERE
STANDARDISE
on Wickham**

**BUILDERS' HOISTS
AND WINCHES**

because

1. They are more dependable—

designed and ruggedly built to reduce wear and tear.

because

2. They take less time to erect—

quick-fitting tower masts are self-aligning; require no fishplates.

because

3. They have a larger effective life

—robust sections throughout . . . self-aligning bearings . . . power units totally enclosed to give complete protection in dusty, adverse working conditions

For full details, apply for illustrated Folder
There's a Wickham Agent in your district !

WICKHAM ENGINEERING CO. LTD

**34 VICTORIA STREET,
LONDON, S.W.1**

Telephone: Abbey 5967/8





The symbol of leadership
in the development
and manufacture of
Prestressed Precast Concrete
in Great Britain



CONCRETE DEVELOPMENT CO. LTD

Office and Works:
Iver, Bucks
Telephone: Iver 809

London Office:
1 Queen Anne's Gate, SW1
Telephone: Whitehall 3111

New floors old floors

{ and the famous ground }
floor one gets in on }

benefit from

EVODE

PROVERS

Part of the job of putting Britain on a sound footing rests squarely on smooth, clean dustless works, mill and factory floors—a high productivity factor, a safety factor too. Evode Provers make concrete and granolithic floors permanent, hard-wearing and dustless. They are specialised products, Prover II for new floors, Prover V for old floors—neither contains silicate of soda.




C.I.E. BUS DEPOT, INCHICORE, DUBLIN:
Main Area—360 ft. x 200 ft.
EVODE MELLITOL incorporated into the mix and
EVODE PROVER II CRYSTALS applied as a surface
treatment afterwards

Write for leaflet P8492 for details of treatment and prices to
EVODE LIMITED GLOVER STREET STAFFORD

Telephone: 1590/1/2
Telegrams: EVODE STAFFORD

DOUGLAS



*Trostre Works, Llanelli, for the Steel Company of Wales.
L. G. Mouchel & Partners, Ltd., Consulting Engineers.*

CIVIL ENGINEERING BUILDING
SITE INVESTIGATIONS
REINFORCED AND PRESTRESSED CONCRETE

ROBERT M. DOUGLAS (CONTRACTORS) LTD.
395 GEORGE RD., BIRMINGHAM, 23. AND BRIDGE RD., WAUNARLWYDD, nr. SWANSEA.

use the **A.B.** **SERVICE** for concrete work

SHUTTER PANELS

All sizes and types

ADJUSTABLE SHORES

for floor and beam support

ADJUSTABLE CENTRE FORMS

for floor support

SHUTTERLOCK WALING CLIPS

For bracing with scaffold tube and locking the panels together, eliminating nuts and bolts in shuttering. Tremendous saving in erecting and striking costs

COLUMN CLAMPS : BEAM CLAMPS

ROAD FORMS : TRENCH STRUTS

We also design and manufacture Steel Moulds for Floor Beams, Piles, Railway Sleepers and all other precast concrete products

Let us solve your problems

A. B. MOULD & CONSTRUCTION CO., LTD.

92 WHITEHORSE ROAD

CROYDON



SURREY

Telephone : Thornton Heath 4947.

Telegrams : Abmould, Croydon.

Makes a better job of it

**easier
quicker
cheaper**



Illustrating Rapid Metal Formwork at intersection of two walls, showing use of internal corner panels.

RAPID METAL FORMWORK

for all concrete construction

Only **RAPID METAL FORMWORK** panels have the patented arris that guarantees a smooth, uniform surface to the concrete. No fins. No rubbing down. Further, this improved Steel Shuttering can be erected or struck easily and quickly by semi-skilled labour. No special tools are necessary. Think what a big saving this means in time, tools and labour. Send coupon below for illustrated brochure and full details of sale or hire terms.

RAPID METAL FORMWORK is ideal for all in situ concrete construction, including double or single-face work, foundations, walls, columns, beams, suspended floors, bases, ducts and rectangular or circular tanks. It is made up from four basic components— $\frac{1}{4}$ " steel straight and corner panels, channel posts and clamps. The panels and channels are available in various sizes, with precision-slotted boundary flanges to take the 3 types of patent clamps.

*Our expert technicians are ever at the service of the Civil Engineering and Building industries, to collaborate and demonstrate the many advantages of **RAPID METAL FORMWORK**. Post coupon for illustrated brochure and full details of sale or hire terms, to Rapid Metal Developments Ltd., 209, Walsall Road, Birmingham, 22b.*

NAME _____

ADDRESS _____


RAPID METAL FORMWORK

Supplied by

RAPID METAL DEVELOPMENTS LTD.

209, Walsall Rd., Perry Barr, Birmingham, 22b.

Telephone: B1 Richfield 6021




GUNITING

The successful way to re-condition defective concrete structures, encase structural steelwork, and line tunnels and water reservoirs. Developed and applied in all parts of the world with the resources, experience and skill of The Cementation Company, Ltd.

PILING

The Cementation Company, Ltd. have the resources and the experience to undertake piling work for Hammer Foundations, Factory Extensions, Machinery Bases, Underpinning, Bridges and any similar purpose in any part of the world. And the skill to complete the work quickly and inexpensively even where headroom and working space are limited and freedom from harmful vibration is essential.




CEMENTATION

For nearly half a century we have, by one or more of our processes, successfully prevented leakage of water through, under and around dams, from service and impounding reservoirs, filter beds, draw-off tunnels and other ancillary works. Our reputation is world-wide.

THE **C E M E N T A T I O N**
Company Limited

BENTLEY WORKS · DONCASTER · TEL. DON. 54177-8-9



Every
well-planned road
laid in
Reinforced Concrete
is a step nearer
to national
highway perfection

BRC

REINFORCEMENT FOR ROADS

Formby By-Pass (Lancashire County Council)

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD
London, Birmingham, Bristol, Leeds, Leicester, Manchester, Newcastle, Cardiff, Glasgow, Dublin, Belfast

SUPER CEMENT

'SUBMARINE BRAND'

THE TANNO-CATALYSED PORTLAND CEMENT

SAVES TIME

SAVES TROUBLE

NATURALLY WATERPROOF, CONTAINS NO WATER REPELLENT MATERIAL

Uses :—

For CONCRETE

Provides a CONCRETE of great strength at early dates and impervious to water, oil, etc., without any form of surface coating.

For PAVING

Produces a hard wearing PAVING, dustless and proof against penetration by water, etc.

For RENDERING

Supplies an impenetrable RENDERING of such adhesive power that a 1" thickness will resist an outside pressure of at least a 20' head of water.

For SLURRY (as paint)

Makes a perfectly watertight covering to brick or breeze concrete walls at very small cost, and also provides the best watertight undercoat to coloured finishes.

Technical Information is available to users.

Used in 1914-1918 and still used by :

Air Ministry, War Office, Admiralty, Ministry of Works, Ministry of Supply, etc.

SUPER CEMENT LTD.,

29 TAVISTOCK SQUARE, Phone :
LONDON, W.C.1 Euston 1808

**CONCRETE
PROOFING
Co. LTD.**

**GUNITITE
SPECIALISTS**

Expert advice and schemes submitted for gunitite work of every kind. Complete information on the various uses of gunitite will be gladly sent on request.

100, Victoria Street, Westminster, S.W.1

Telephone :

VICTORIA 7877 and 8278

2,100,000 CUBIC YDS. OF AIR-ENTRAINED CONCRETE

AT THE
BULL SHOALS
DAM
U.S.A.



MAKE GOOD CONCRETE BETTER WITH AERACON A.E.A.

INCREASED PLASTICITY, WORKABILITY & DURABILITY. RESISTANCE TO PASSAGE OF WATER & FROST ATTACK. NON-SEGREGATION OF AGGREGATES & EASIER & FASTER PLACING ARE JUST A FEW OF THE ADVANTAGES OBTAINED WHEN CONCRETE IS AIR-ENTRAINED. NOW AVAILABLE IN GREAT BRITAIN UNDER THE TRADE NAME OF AERACON A.E.A.


For Information on this
Air-entraining Agent
write to

G. FISHER (FALLOWFIELD) LTD.

ALBANY WORKS, ALBANY ROAD, CHORLTON-CUM-HARDY

Telephone : Chorlton 1063.

Manchester 21



**Essential to all users
of concrete!**

the **ACROW**
WIGMORE CONSISTOMETER

*A really practical machine for quickly
and accurately measuring WORKABILITY*

Write now for
full particulars to:-
ACROW
(Engineers) Ltd.

{ South Wharf, Paddington, London, W.2 (Ambassador 3456)
130 Coventry Drive, Glasgow, E.I. (Bridgeton 1041)
22-24 City Road, Bristol, 2 (Bristol 24595)
West Stanley Street, Manchester, 5 (Trafford 2965)
Lupton Street, Hunslet, Leeds, 10 (Leeds 76514)
Carl Street, Walsall, Staffs. (Walsall 6296)
78 Duncruce Street, Belfast (Belfast 45211)

dustless floors

Concrete dust is fatal to machinery, a severe inconvenience to operatives and a constant menace to production.

"CCC CASEHARDENING" process produces a floor which is not only hard—*so hard that even by the drastic use of a wire scratch broom no concrete dust can be raised*—but is also impervious to water and resistant to the destructive action of oils, grease and soda.

"CCC Casehardening" process is applied only by our trained staff and the result is guaranteed.


"CCC" PREMIX for Waterproofing, Rapid Hardening,
and Toughening Concrete

**CONCRETE
CASEHARDENING
CO. LTD**




CRESCENT WHARF · BIRMINGHAM · I

L.G.B.




Reinforced Concrete Building constructed for
HUMPHREYS & GLASGOW LTD.
at the
NORTH THAMES GAS BOARD'S BECKTON WORKS

PETER LIND & CO LTD
STRATTON HOUSE, PICCADILLY, W.1



Not by its fair surface but by its hidden strength is concrete to be judged. Here's why, increasingly, good specifications for road and airfield and building foundation call for an underlay of IBECO waterproof concreting paper. There's no better insurance for even hydration, sound setting, all-through strength, long life.



IBECO

COMPLETELY WATERPROOF CONCRETING PAPER

MADE BY C. DAVIDSON & SONS LTD • MUGIEMOSS • ABERDEENSHIRE

**REINFORCED CONCRETE
GRANOLITHIC PAVINGS**

CAST STONE

STAIRCASES

FLOORS

in-situ and precast

STUART'S

GRANOLITHIC CO. LTD.

FOUNDED 1840

LONDON

26 West End Avenue, Pinner, Middlesex

BIRMINGHAM

Northcote Road, Stechford


MANCHESTER

Ashton Road, Bredbury, Stockport

EDINBURGH

46 Duff Street

Twice round the clock...



concrete sufficiently hard for almost any purpose

On new and urgent work, use '417 Cement.' On repairs to services—roads, sewers, railways—that must be reinstated without delay, use '417 Cement.' Concrete made with this cement is ready for almost any duty in 24 hours—and for many in a good deal less. For example, in a temperature of 60°-65°F., concrete road foundations can be surfaced within 24 hours and opened to traffic immediately; concrete floors can be used for foot traffic in 12 to 16 hours. Concrete made with '417 Cement' is less liable to damage by frost. Please write for full details.

'417 cement'


QUICK SETTING — EXTRA RAPID HARDENING

THE CEMENT MARKETING CO. LTD., Portland House, Tothill Street, London, S.W.1
or G. & T. EARLE LTD., Cement Manufacturers, Hull

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD., Penarth, Glam.

MILFORMS

**FOR AUTOMATIC ALIGNING AND
SELF-SUPPORTING SHUTTERING TO
WALLS, FLOORS, COLUMNS AND BEAMS, ETC.**



Inspection of the actual plant will show the simple and robust nature of the equipment which has been designed for rapid fixing and easy maintenance.

This new range of formwork, for use on all types and systems of concrete construction, provides the Contractor with the means of overcoming formwork difficulties in an easy and economical way. No special tools are required, it is easy to erect and dismantle, and robustly constructed to withstand heavy wear. Full information can be obtained from any Mills Depot.

MILLS
SCAFFOLD CO., LTD.

BELFAST • BIRMINGHAM • BOURNEMOUTH • BRIGHTON
BRISTOL • CANTERBURY • CARDIFF • COVENTRY • CROYDON • DUBLIN
GLASGOW • HULL • ILFORD • LIVERPOOL • LOWESTOFT • MAN-
CHESTER • NEWCASTLE • NORWICH • PLYMOUTH • PORTS-
MOUTH • SHIPLEY • SOUTHAMPTON • SWANSEA • YARMOUTH

Head Office & Depot: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6. Tel: RIVerside 5026/9



Ruberoid C. and E. Jointing provides the necessary resilience to allow concrete structures of all types to move under temperature variations without building up dangerous stresses. Where a 'single operation' material is required Ruberoid C. and E. Jointing can be relied upon to give complete satisfaction. Available in lengths up to 6 ft., thicknesses from $\frac{3}{8}$ to 1 in. and depth to suit the concrete.

Use Ruberoid, the original Concreting Paper in the road bed. It prevents absorption of liquid cement into the sub-base and aids free movement of the slab.

a product of:

THE RUBEROID COMPANY LTD.,

187, COMMONWEALTH HOUSE, NEW OXFORD STREET, LONDON, W.C.1



C.E.113



DELIVERED DIRECT TO ANY
CONTRACT BY MOTOR LORRY.

Quotations on Application.

Telephone: Paddington 2024 (3 lines).

WASHED
BALLAST, SAND, SHINGLE &
Crushed Aggregate for Reinforced Concrete.

WILLIAM BOYER & SONS, LTD.

Sand and Ballast Specialists,
**IRONGATE WHARF,
PADDINGTON BASIN, W.**

MEMBERS OF B.S. & A.T.A.

AQUAREP

SEND FOR
DETAILS

for **100%**
**WATERPROOF
CONCRETE**

DAMP-PROOFING LTD.


DEPTFORD Tel. Tideway 1486-7 LONDON, S.E.



**FOR ROAD
REINFORCEMENT**

CHRISTIANI & NIELSEN LTD

REINFORCED CONCRETE



Pile Driving for Reinforced Concrete Jetty

54 VICTORIA STREET,

LONDON, S.W.1.

TELEPHONE: VICTORIA 6152


POWER BAR BENDERS

FOR ALL SIZES OF REINFORCING BARS


STANDARD PRODUCTION MODELS

The ARD. 50 MODEL—as illustrated on right—has a capacity for cold bending Mild Steel Bars up to 2" dia. and incorporates a second Bending Head to give high-rate bending for small diameter bars.

The RAS. 40 MODEL shown below is a single disc machine of exceptional performance. With a capacity for 1½" dia. bars, it bends at highest practical rate—e.g. a full hook takes only 3 seconds bending time.



*Ensure accuracy, economy
& simplicity of operation*



INTERESTING FEATURES

Either of the Models illustrated can be supplied motorised or engine driven.

Standard Accessories supplied include all necessary Formers and Bending Pins, a special Backrest for simultaneous bending of a number of small diameter bars, and Accessories for forming right-angle loops in one operation.

Special Safety Device incorporated to prevent damage to mechanism if overloaded.

The desired Bending Angle may be set mathematically, and this is of great assistance in Repetition Bending.

CEMENT & STEEL LTD.

SECOND AVENUE

CHATHAM

KENT


Telephone: Chatham 45580

Telegrams and Cables: Cembelgi, Chatham

1

Prestressed Concrete (Lee-McCall System) with Macalloy Bars

An economical and effective system of prestressing concrete, using high-tensile alloy steel in bar form. The steel is provided with positive end-anchorage and does not rely upon bond to transmit the stresses to the concrete.



YOU CAN
constructional
SAVE STEEL

by using . . .


REINFORCEMENT by McCALLS

**Write for further
details**

2

'Matobar' Welded Fabric Reinforcement

Economical for all types of concrete construction. Hard drawn, high-tensile steel wire mesh, electrically welded at every intersection; permissible working stress, 27,000 lb. per sq. in. in tension.



3

Isteg Steel Reinforcement
manufactured under licence

Steel bars with a combination of twist and cold working, giving 50% improvement in tensile stress; 30% less weight of steel. Improved bond; hooks and overlengths eliminated.

McCALL & CO (SHEFFIELD) LTD.

TEMPLEBOROUGH, SHEFFIELD, AND AT LONDON

TRANSPORT BY ROPEWAY

This Ropeway is carrying Bauxite over Indian roads, valleys and hills for a distance of 6 miles. We can install ropeways to carry a few hundred-weights or up to 400 tons per hour, and if you have any transport problems, we invite you to consult us. *Our Engineers have solved many similar problems; can they help you to solve yours?*

BRECO
ROPEWAYS



Write for illustrated brochure

**BRITISH ROPEWAY
ENGINEERING CO LTD**

Plantation House, Mincing Lane, London, E.C.3

Telephone: Mansion House 4681-2

Telegraphic Address: Boxhauling, Fen, London



THE "JOHN BULL" CONCRETE BREAKER

NEW "B.A.L." TYPE.

INCREASED :—

PENETRATION, RELIABILITY, LIFE.

REDUCED :—

VIBRATION, NOISE AND WEAR.

**THESE ARE THE SALIENT FEATURES
OF THE NEW CONCRETE BREAKER**

★ ★ ★

REAVELL & CO., LTD.

RANELAGH WORKS, IPSWICH.

TELEGRAMS: "REAVELL, IPSWICH."

TELEPHONE: 2124



PRESTRESSED CONCRETE UNITS

FORMING

TRUNK ROAD BRIDGE

Photograph by
permission of
Lincolnshire
C.C.

ANOTHER

ANGLIAN

PRESTRESSED PRODUCT

**PYLONS • PILES AND
SHEET PILES • ROAD
AND RAIL BRIDGES
ROOF & FLOOR BEAMS**

ANGLIAN BUILDING PRODUCTS LTD • LENWADE 15 • NORWICH • Tel. : Gt. Witchingham 91

MOULD OILS & COMPOUNDS

for every process of
concrete production

CONCREAM

This non-staining, smooth and easy working white mould oil can be used with confidence on all classes of in situ and precast concrete work where the use of a white mould oil is recommended.

VIBRAMOL

This non-staining and non-separating mould oil is made specially for use on steel shuttering and moulds where vibrators are used, and provides a good film which is not readily moved under vibration.

SPRAYMOL

This grade of mould oil has been specially produced for use with a spray gun. It can be used with great economy on all types of shuttering and moulds, and will not separate under pressure.

"P.S."

Experience has shown that the production of precast and in situ prestressed concrete needs a special mould compound, and in collaboration with leading prestressed specialists we have produced Grade "P.S." Mould Compound for this class of work.

"8.A."

This Mould Compound has been specially produced to satisfy the requirements of those engaged in the production of spun concrete products.

CONCREAM Regd.
VIBRAMOL Regd.
SPRAYMOL Regd.
"P.S." & "8.A."

PRODUCTS OF THE ORIGINAL MAKERS OF CONCRETE MOULD OILS

We specialise in the production of mould oils and compounds for concrete work of every kind, from mass concrete work to high-class architectural stone work, and have an unrivalled experience which enables us to give expert advice on all mould oil problems. We have a grade for every purpose, and will be pleased to submit full details, samples, and prices on request.

RICH^d HUMBLE & SON, LTD., COLUMBA OIL WORKS, LEEDS, 3

Telephone : 27155.

ESTABLISHED 1854.

Telegrams : "Columba, Leeds, 3."

CONCRETE

Concrete made with Ciment Fondu is completely immune to Sulphates and highly resistant to many other forms of chemical attack.

& SULPHATES




The best cement in the world for speed, strength and resistance.

In addition to its immunity to sulphate attack, concrete made with Ciment Fondu is ready for any use at 24 hours. Used with crushed firebrick for refractory purposes it is non-shrinking, non-spalling, stable under load at 1300° C. and can be cold-cast to any shape.

LAFARGE ALUMINOUS CEMENT CO. LTD.

73, BROOK STREET, LONDON, W.1. TELEPHONE: MAYFAIR 8546



The PC3 PUMCRET *Mobile* **CONCRETE PUMP**

CONCRETE BY PUMP AND PIPELINE

- ★ The latest and most efficient method of placing concrete for Hydro-Electric Schemes, Tunnels, Power Stations, Cooling Towers, Subways, Silos, Canals, Piers, Viaducts, Reservoirs, Bridges, Runways, Foundations, Buildings, Pylons, Pipe Spinning and Lamp Columns.
- ★ Pumpable concrete must of necessity be good concrete.
- ★ Pumps and Mixing Plant can be located at the most convenient position within the pumping range.
- ★ The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.
- ★ All "Pumcret" surfaces in contact with concrete are renewable.

Specifications :


Two Sizes :	P.C.3	P.C.4
Capacities per hour, approx.	20-24 cu. yd.	8-10 cu. yd.
Range :		
Horizontal, approx.	1500 ft.	1250 ft.
or Vertical, approx.	135 ft.	125 ft.
Pipeline	6" i.d.	4½" i.d.
Power Required :		
Electric or Diesel .	45 h.p., 60 h.p.	25 h.p.

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone : Western 3546.

Telegrams : Pumcret, Kens, London.



W & C FRENCH LIMITED

Contractors for civil engineering works

BUCKHURST HILL ESSEX

HEAD OFFICE: 50 EPPING NEW ROAD, BUCKHURST HILL, ESSEX. 'Phone: BUCKHURST 4444 (15 Lines)

LONDON OFFICE: 47, VICTORIA STREET, WESTMINSTER, S.W.1

BRANCH OFFICES

ROMFORD
217 Branwood Rd., Romford
Tel. Romford 2826

WISBECH
South Brink, Wisbech
Tel. Wisbech 1520

COLCHESTER
Ipawich Rd., Dedham
Nr. Colchester
Tel. Dedham 2264

KENYA
P.O. Box 6032, Nairobi, Kenya.
Lighterage and Wharfage facilities
on River Lea.

BRICKFIELDS AT

Chigwell Rd., S. Woodford,
E.16
Tel. Buckhurst 1376

Luxborough Lane, Chigwell
Tel. Buckhurst 5833

Ongar, Essex
Tel. Ongar 48

Makers of Stock Bricks, Facing
Bricks, Roof Tiles, Land Drains
and other clay products.

TRANSPORT AND PRE-CAST CONCRETE DEPARTMENT

North Farm,
Loughton, Essex.
Tel. Loughton 480.


CONTRACTORS FOR

Air Ministry,
London County Council,
Railway Executive
British Railways,
Catchment Boards,
London Transport Executive,
Colne Valley Sewerage Board,
Middlesex County Council,
East Middx. Main Drainage,
New Town Corporations and
other Authorities.

GLASCRETE

Reinforced Concrete and Glass

STANDARD LANTERN LIGHTS



In precast
units for easy
assembly by Builder

For full particulars please write
for leaflet P.39D.



J.A. KING & CO. LTD.

181, Queen Victoria St., LONDON, E.C.4

Telephone: CENTRAL 5866 (6 lines).



**PIN YOUR FAITH
TO THE TESTED
BRAND.**

THIS LABEL ON
EVERY BARREL
CARRIES WITH IT
FORTY YEARS'
EXPERIENCE OF
MANUFACTURE.

**NONE OTHER IS
"JUST AS GOOD"**

THE LEEDS OIL & GREASE CO.

'Phone 22480

LEEDS, 10

'Grams: "Grease."



VIBRATING EQUIPMENT for QUALITY CONCRETE

**PETROL & ELECTRIC
VIBRATING
TAMPERS
SALE OR HIRE**

Details of these and other vibrating plant sent on application.

Manufacturers of vibrating tables, internal vibrators, external vibrators, petrol and electric vibrating tampers, vibrating screens, pan vibrators, electric motors, petrol engines, builders' hoists and winches, and hydraulic bar croppers.



E. P. ALLAM & CO. LTD.

LONDON: 45 Great Peter Street, S.W.1. Telephone: Abbey 6353 (5 lines)

SCOTLAND: 39 Cavendish St., Glasgow, C.S. Tel.: South 0186. Works: Southend-on-Sea. Tel.: Eastwood 52243




CONCRETE REINFORCEMENT

BENT TO SPECIFICATION

In 9 months we manufactured and supplied to the British Cast Concrete Federation, reinforcement for the M.O.W. Standard Hut involving 60,000 cut, bent and welded cages, and 5,000,000 stirrups, and therefore rightly claim to be specialists in the production of all types of cages where reinforced concrete is required. Whether for use in Garages, Runways, Docks, Warehouses, Forecourts, etc., "bending is carried out to your own Specification."

**CAGES FOR
PRECAST
CONCRETE**

**CAGES FOR
REINFORCED
CONCRETE
FRAMEWORK**



SOMMERFELDS LTD.

WELLINGTON, SHROPS. Telephone: 1000 (5 lines)

& 167 VICTORIA ST., S.W.1 Telephone: VIC 1000



FORD ENGINES



for

INDUSTRIAL EQUIPMENT



Ford Industrial engines are widely used in providing power for Industrial Machinery of every description and have a power range between 10 and 60 B.H.P. when required for continuous working purposes. They are inexpensive to buy and economical to run. They give you long and trouble-free service, and what little maintenance they need is promptly and speedily carried out by Ford Service, which covers every part of the country. This combination of a first-class product and first-class service is the reason why Ford engines hold an unchallengeable reputation in every branch of industry. The advice of our Industrial Unit Department is freely at your disposal.

Why not discuss *your* power problems with us?



FORD MOTOR COMPANY LIMITED • DAGENHAM • ESSEX

REINFORCED CONCRETE CONSTRUCTION



These Photographs

(by courtesy of North Western Gas Board)

Illustrate :—

REINFORCED CONCRETE RETAINING WALLS.

RECENTLY CONSTRUCTED BY US
NEAR MANCHESTER.

WE ARE ALWAYS PLEASED TO
QUOTE FOR :—

**HEAVY
EXCAVATION.
FOUNDATIONS.
REINFORCED
CONCRETE.**





UNITED KINGDOM CONSTRUCTION
CIVIL ENGINEERING CONTRACTORS

CONCRETE PILING


LIMITED

CIVIL ENGINEERING CONTRACTORS



Specialists in the construction
of all forms of reinforced
concrete structures for
Industrial and Public Services.

10, WESTMINSTER PALACE GARDENS, ARTILLERY ROW, LONDON, S.W.1. - ABBEY 1626
LADAS DRIVE BELFAST - BELFAST 58100 • WORKS: RIVER RD. BARKING - RIPPLEWAY 2624



Reinforcement by T.C. Jones & Co. Ltd

REINFORCEMENT ENGINEERS • STRUCTURAL ENGINEERS

WOOD LANE, LONDON, W.3. Phone: SHE 3031
600
ROUTE STREET, CARDIFF • TREDEGAR, GLAM.



GUNITE AND CEMENTATION



Systematic repairs to structures based on systematic diagnosis of defects.

WHITLEY MORAN & CO. LTD.

Specialists in the Repair of Engineering Structures

GUNITE

5 OLD HALL STREET, LIVERPOOL.

Telephone: Central 7975

A NEW "CONCRETE SERIES" BOOK

"CONSTRUCTION WITH MOVING FORMS"

By L. E. Hunter, M.Sc., A.M.Inst.C.E.

72 pages. 53 illustrations.

Price 7s. 6d.; by post 8s. 1.75 dollars in Canada and U.S.A.

Describes and illustrates practical methods of rapid construction with continuously-moving, or sliding, forms. This book will be of assistance to those familiar with the process, and will prevent mistakes being made by those using moving forms for the first time.


PRINCIPAL CONTENTS

- Construction of wooden and steel forms, yokes, and jacks.
- Details of deck, scaffolds, dragging at corners, circular and polygonal bins, and lateral bracing.
- Procedure of construction: Preliminaries. Levelling. Roof. Dismantling.
- Materials. Plant. Reinforcement. Construction in cold weather. Emergency equipment. Labour.
- Reinforcement: Design. Stacking. Cover. Bar schedules.
- Special applications: Structures of variable shape. Structures with floors. Structures without columns. Openings in walls. Tanks. Chimneys. Coast.
- Shutters Travelling Horizontally: For sea walls, culverts, and sewers.
- Hints and Reminders.

CONCRETE PUBLICATIONS LIMITED

14 Dartmouth Street, London, S.W.1, England

REINFORCED CONCRETE CHIMNEYS by CUSTODIS



Custodis skilfully design and erect special-purpose chimneys for any industry.

A typical example is at the new Esso refinery at Fawley. The illustration shows one chimney which is 250 ft. high, with outside diameters of 12 ft. at the top and 19 ft. at the base. It is lined with refractories and special acid-resisting bricks, besides having special protection at the top. Four other chimneys are also specially designed and lined.

Chimney for the single-stage Crude Unit.

CUSTODIS (1922) LTD

119 VICTORIA STREET, LONDON, S.W.1

Telephone: VICTORIA 0779. Telegrams: "CUSTODOMUS · SOWEST · LONDON"

★ CHASTON

**SPECIALIST CONTRACTORS
FOR REINFORCED CONCRETE
AND PRECAST PRODUCTS**


WE INVITE YOUR
ENQUIRIES FOR CON-
CRETE WORK OF ALL
KINDS, IN STANDARD
OR SPECIAL DESIGNS

PRESTRESSED STRUCTURAL UNITS

DAVID CHASTON LTD., ESSEX ROAD, HODDESDON, HERTS.

Telephone: Hoddesdon 2264 (3 lines).

"CAPCO" H. F. VIBRATOR



for compacting mortar cubes
for Compression Test B.S.
12/1947, B.S. 915/1947,
B.S. 146/1947, B.S. 1370/
1947. New type automa-
tic control—optional. The
vibrator illustrated in the
B.S. was built in our works.

The "CAPCO" range of con-
crete testing apparatus also
includes Cube Moulds; Slump
Cones; Tensile, Vicat, and Cylin-
drical Moulds; Tile Abrasion
Machines; Compacting Factor
Apparatus.

Full details on request.

CAPCO (SALES), LTD.

BEACONSFIELD ROAD, LONDON, N.W.10.

Telephone: WILLESDEN 0067-8. Cables: CAPLINKO, LONDON

(Sole Agents for all
"Capco" Products)



A new type immersion vibrator
Petrol or Electric

★ *FASTER PLACING -
BETTER CONCRETE -
LOWER MAINTENANCE COSTS*

THE HIGH-FREQUENCY VIBRATOR
WITH THE SLOW-SPEED DRIVE



10,000/12,000

Vibrations per minute

● Send for descriptive leaflet ●



VIBRATOR Dept., PORDEN RD., BRIXTON, LONDON, S.W.2

Tel. : Brixton 3293 (9 lines)

and at Brentford



*We are Specialists in the Repair and
Reconditioning of Defective Reinforced
Concrete Structures, etc.:*

THE
GUNITE
CONSTRUCTION CO. LTD.

WESTERN HOUSE, HITCHIN, HERTS.


Tel. HITCHIN 571.

ACROW

ADJUSTABLE STEEL COLUMN CLAMPS

... for supporting temporary shuttering to reinforced concrete columns and concrete casings to steel stanchions. By using Acrow Adjustable Steel Clamps for supporting column shuttering the amount of timber used is reduced to a minimum with corresponding reduction in labour costs and wastage of material. The accuracy and strength of the Clamps ensure columns of perfectly uniform cross-section throughout. In three sizes covering a range of column dimensions from 10 ins. to 4 ft.

**Use them and reduce costs
FOR SALE OR HIRE**



All enquiries to :—**ACROW (ENGINEERS) LTD.**, South Wharf, Paddington, London, W.2. (Ambassador 3456).
130 Coventry Drive, Glasgow, E.1. (Bridgeton 1041) ● 22-24 City Road, Bristol, 2 (Bristol 24595)
West Stanley Street, Manchester, 5 (Trafford 2965) ● Lupton Street, Hunslet, Leeds, 10 (Leeds 76514)
Carl Street, Walsall, Staffs. (Walsall 6296) ● 78 Duncrue Street, Belfast (Belfast 45211)

SAVE TIME, LABOUR and MATERIALS
by supporting your **TRENCHES** with




ACROW
ADJUSTABLE STEEL
TRENCH STRUTS
&
STEEL
TRENCH SHEETING

Regd. Design No. 852839

AVAILABLE
IN 4 SIZES

1'0" exp. to 1'6"
1'6" " " 2'3"
2'4" " " 3'6½"
3'4" " " 5'6"



In lengths
up to 12 feet
Overall width 13½"

All enquiries to:
ACROW (ENGINEERS) LTD.

for addresses see above.

Cut costs;
be more competitive;
use **ACROW**
ALL-STEEL. ADJUSTABLE
FLOOR-CENTRES
Erected in one-eighth of the time
taken by the timber method

The cam-operated retractable bearer-plates make Acrow Floor-Centres THE FASTEST IN USE.

★
In 4 sizes, which, between them, provide for any span ranging from 4 ft. to 15 ft.

★
For sale or hire

All enquiries to: **ACROW (ENGINEERS) LTD.**
South Wharf, Paddington, London, W.2 (Ambassador 3456)
130 Coventry Drive, Glasgow, E.1 . . . (Bridgeton 1041)
22-24 City Road, Bristol, 2 . . . (Bristol 24595)
West Stanley Street, Manchester, 5 . . . (Trafford 2965)
Lupton Street, Hunslet, Leeds, 10 . . . (Leeds 76514)
Carl Street, Walsall, Staffs. . . . (Walsall 6296)
78 Duncrue Street, Belfast (Belfast 45211)

(1) As used for Hollow-tile floor construction.

(2) As used with Acrow Floorforms or Ferroforms for solid reinforced concrete floor construction.

(3) Alternative method for solid floor construction with Floor-Centres tight up against each other.

ACROW—THE Specialists in Steel Shuttering & Propping

STENT PILES

USED FOR THE NEW 150 ft. FACTORY
EXTENSION FOR FORD MOTOR
COMPANY LTD., DAGENHAM.



- ★ THEY'RE SAFE
- ★ THEY'RE ECONOMICAL
- ★ LARGE RANGE OF STOCK SIZES

Technical details
supplied on request to:-

STENT

PRECAST
CONCRETE
LTD.


Sales: 1 Victoria Street, S.W.1. Phone: Whitehall 2573

Works: Dagenham Dock, Essex. Phone: Rainham (Essex) 780

Midland Agent: Fabian J. M. Jackson, M.In.B.E., M.I.P.E., 11 Leicester Road, Loughborough. Phone: Loughborough 3781 and 3543. 56 St. Mary's Road, Manchester, 10. Phone: FAI 2623.



Photographs by kind permission of Ford Motor Company Ltd.




KENNEDY BENDING MACHINES

... featured above is the 1213 Bar bending machine for the accurate and rapid cold bending to precise measurement of mild steel reinforcing bars of up to 1" diam.

For full particulars of this and other
Kennedy benders write to:-

W. KENNEDY LTD., Dept. C, STATION WORKS,
WEST DRAYTON, MIDD. Phone: West Drayton 2084



Trent Gravels

10,000 tons per week

Washed & Crushed 1½ in. to ¼ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTTS

Telephone: Beeston 54255.

"CONCRETE SERIES" BOOKS ON CONCRETE

For a complete catalogue giving prices in sterling and dollars, send a postcard to:

CONCRETE PUBLICATIONS, Ltd.
14 Dartmouth St., London, S.W.1



A symbol of quality materials, experienced workmanship, expert supervision, and excellent service.

for all forms of **PRECAST CONCRETE**

We specialise in the production of Precast Concrete structural members to standard or special designs, also products for the Electrical Industry, Sports Ground Contractors, and Fencing Contractors, and shall be pleased to submit quotations for your requirements.

H.B. CONCRETE CO. LTD.

Head Office and Works : VICARAGE ROAD, EGHAM, SURREY. Telephone : Egham 3092.

GUNITE SPECIALISTS

WM. MULCASTER & CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

CREWE

Telephone : Crewe 2265-6.

THE DISPLACEMENT METHOD OF FRAME ANALYSIS

By G. P. MANNING, M.Eng., M.Inst.C.E.


128 pp. 88 illustrations. 19 tables. Price 9s ; by post 9s. 9d.
2.10 dollars in Canada and U.S.A.
Published 1952.

Full details and many examples of the application of the "Displacement Method" of analysis of indeterminate frames, which has been proved in practice in a large design office for more than fifteen years. This labour-saving method can be applied to simple and complex frames, closed frames, and continuous beams of constant and non-constant section. Solutions are obtained by slide-rule, time is saved and the risk of errors is reduced.

- (1) Full discussion of the principles of the Displacement Method.
- (2) Application, with examples, of the method to—
 - (i) Rectangular frames with members of constant section ;
 - (ii) Frames with sloping members of constant section ;
 - (iii) Multiple-bay and multiple-story frames with members of constant section ;
 - (iv) Settlement and shrinkage ;
 - (v) Simple frames with members of non-constant section ;
 - (vi) Brackets on columns ;
 - (vii) Complex frames with members of non-constant section ;
 - (viii) Continuous beams.
- (3) Tables for fixed-end bending moments and shearing forces and elastic constants for members of constant section, for members with parabolic soffits, straight splays, curved splays, deep ends, or uniform taper, and for members with two parts of constant section.

PUBLISHED BY

CONCRETE PUBLICATIONS LIMITED
14 Dartmouth Street, London, S.W.1, England



Goodenough.

PORTABLE PUMPS

*Simplicity of design.....
robustness of construction..
ease of manœuvrability.....
combine to make a pumping
set of unsurpassed quality
and performance.....
Your pumping problem can
be solved by a pump from
the Goodenough range.*

Telephone:
POPESGROVE
7354 & 5340
Telegrams:
GOODENOUGH,
TWICKENHAM

GOODENOUGH CONTRACTORS' MACHINERY LTD
70-72 LONDON ROAD TWICKENHAM
MIDDLESEX ENGLAND



*Candy Filter House for South-West Suburban Water Company.
Mr. H. Austin Palmer, Engineer.*


THE BEST WAY to illustrate CONCRETE
is by HALF-TONE BLOCKS
OF THE HIGHEST QUALITY

Complete Service of
ENGRAVING, TYPESETTING,
PHOTOGRAPHY,
ELECTROTYPING and STEREO-
TYPING and ARTISTS' WORK

THE STRAND ENGRAVING COMPANY LIMITED
8 & 9 ESSEX STREET, STRAND, W.C.2

Telephone: Temple Bar 6311.

Engravers to "Concrete."



CHISLEHURST & SIDCUP BLACKFEN
COUNTY SECONDARY SCHOOL
FOR BOYS, KENT COUNTY COUNCIL

E. B. Musman, B.A., F.R.I.B.A., Architect, in collaboration with S. H. Loweth, F.S.A., F.R.I.B.A., Kent County Architect.

RUSH & TOMPKINS LTD.

SIDCUP · LONDON · BIRMINGHAM · DURBAN, NATAL

formerly KENT & SUSSEX CONTRACTORS, LTD.

PROMETO

(REGD. TRADE MARK)

moving-forms

for monolithic concrete construction



**a rapid and
highly economical
method of erecting
structures of all kinds**

PROMETO hydraulically controlled moving forms and equipment enable a high rate of construction to be maintained with minimum labour requirements. They provide the means of making substantial savings in the cost of erecting Silos, Chimneys, Water Towers, Multi-Storey Flats, the lining of Mine and similar shafts, Elevator Houses, and many other types of structures. We have the sole rights for the manufacture and use of PROMETO equipment in the United Kingdom and are prepared to enter into sub-licence arrangements with selected Contractors for individual jobs or prescribed districts. Enquiries are invited from Consulting Engineers and Architects.

WILLIAM

THORNTON & SONS LTD
WELLINGTON ROAD
LIVERPOOL

Building and Civil Engineering Contractors

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume XLVII. No. 7.

LONDON, JULY, 1952

EDITORIAL NOTES

Aeronautics and Civil Engineering.

AT first sight there does not seem to be a very close connection between concrete construction and aircraft design, and probably not many civil engineers engaged on research, design, or civil engineering construction realise that without their work high-speed flight would be impossible. This was one of the points made in the last Wilbur Wright Memorial Lecture * to the Royal Aeronautical Society. The phenomenal performance of present-day aircraft, the lecturer said, had not been exclusively due to those who actually designed and built the aeroplanes, for the best designers of to-day could do very little better than the Wright brothers if they were limited to the materials, constructional methods, and equipment of fifty years ago. Explaining the importance of constructional engineering to air transport, the lecturer referred to a calculation made by Hermann Glauert, one of the most brilliant British aeronautical scientists of the 1920's, "who established the thesis that the stalling speed of an aeroplane could not be less than about one-quarter or one-fifth of its maximum flying speed, and no means had then been devised for landing aircraft at lower speeds. This meant that landing speeds in excess of a hundred miles an hour were adopted from necessity. Long concrete runways were therefore no less essential to the supersonic aircraft of to-day than the jet engines which propelled them." The resources of constructional engineering are also at the service of atomic scientists in the design of concrete shields to confine the extraneous nuclear radiation which cannot at present be controlled and directed to the production of useful work.

It would be unrealistic to suppose that the place of concrete in the development of atomic energy is any more than a minor and subsidiary adjunct of the atomic piles and reactors, just as in conventional power stations the steam turbines and the generators are the vital elements rather than the chimneys and cooling towers. However, this subordination of the constructional element to the mechanical, electrical, and scientific must not lead civil engineers to restrict their interest to structures in which the constructional features predominate. It is as necessary that research should be directed to reducing the thickness of a runway, or of an atomic screen, as it is to increase what are now considered to be the

* "Prophecy and Achievement in Aeronautics." 40th Wilbur Wright Memorial Lecture, read before the Royal Aeronautical Society at the Institution of Civil Engineers by Sir Harry M. Garner, K.B.E., C.B., M.A., Chief Scientist, Ministry of Supply.

longest economic span of a girder or height of a column. For this reason, designers of runways and the ancillary equipment of mechanical and chemical engineering plant will be grateful for the recognition accorded in this lecture to their work on airfields.

The extent of a high-speed aeroplane's dependence on civil engineering was summarised by the lecturer when he referred to long and expensive runways as "stupendous millstones around the necks of military and civil operators", which were proving an intolerable burden. Indeed so heavy was this burden that those concerned with flying were already considering the possibilities of a new type of flying machine capable of taking-off and landing vertically, a development which would depend on the production of an engine thrust greater than the weight of the aircraft. Another method of avoiding expensive runways is, of course, a greater dependence on flying boats, especially for civil transport. "The construction of larger and larger costly land aerodromes, using land that would otherwise be available for agriculture and industrial use, must surely be found to be too great a price to pay for the convenience of civil aviation." If, as the lecturer envisaged, the limit has been reached in conventional runway construction, new constructional problems will arise in connection with the operation of novel types of land plane and larger flying boats, and constructional engineers must be ready to meet and solve these problems as they arise.

Discussing the comparatively recent achievement of supersonic flight the lecturer said: "The excessive rise in 'drag' as the speed of sound is approached, with the associated loss of stability and control, led to what was known as the 'brick-wall barrier'. Scientists thought that not only would flight at speeds beyond that of sound be difficult, but that flight in the region near that of sound would be highly unstable and dangerous. If sufficient thrust could be provided to enable the aircraft to pass through this dangerous region quickly there might not be time for the lack of stability and control to make itself felt. But there was doubt whether this passage of the barrier would ever be more than a dangerous experimental technique." That was the problem which confronted aeronautical scientists only a few years ago. Now the problem has been solved, and the lecturer continued: "Subsequent developments have shown that the difficulties of transonic and supersonic flight are not so serious as the scientists had thought." Here is a lesson to be learned and an example to be marked not only by those engaged in aeronautics but by scientists and engineers in all branches of engineering. A "brick-wall barrier", which appeared to be an insurmountable obstacle, later lost its apparent invincibility. Constructional engineers have a long-standing and continuing reputation for their refusal to be daunted by difficulties, as the achievements of I. K. Brunel, Sir Benjamin Baker, Sir Donald Bailey, and many others bear witness, but it is well to be reminded by one of the foremost authorities in another branch of endeavour and achievement that there are few "brick-wall barriers" that cannot be demolished or surmounted by the scientist or the engineer if he bring to his task a sufficient measure of confidence, determination, and skill.

Rectangular Slabs Spanning in Two Directions.

Analysis by Pattern of Fractures.

By Professor H. CRAEMER (ALEXANDRIA).

THE principles of the analysis of a reinforced concrete slab supported along two or more sides were dealt with by the writer in this journal for August, 1950. In the following, these principles, which are based on a consideration of the pattern of the fractures at failure of the slab, are applied to rectangular panels supported on four sides and carrying a uniformly-distributed load or a trapezoidal load, and a slab supported on three sides carrying a triangularly-distributed load.

Slab supported on Four Sides : Uniformly-distributed Load.

The pattern of the fractures of a rectangular panel has been frequently shown by tests to be as in Fig. 1, the fragments being ABFE, CDEF, AED,




Fig. 1.




Fig. 2.

and BCF, formed by fractures along the lines AED, BFC, and EF. Sometimes the fractures fork near the corners, but the effect on the load-carrying capacity of the slab is negligible. In Fig. 1, l_x and l_y are the lengths of the sides of the

panel of a slab of constant thickness, and $\frac{l_y}{l_x} = r$. The reinforcement in the

bottom of the slab is assumed to produce a moment of resistance m_x at failure for the bars parallel to l_x , and m_y for the bars parallel to l_y ; m_x and m_y are the moments for unit length. If there is reinforcement in the top of the slab at the supports, the lines of the supports are also lines of fracture and the corresponding moments of resistance are m'_x , m'_y , m''_x , and m''_y on unit length of AB, CD, AD, and BC respectively.

Generally, the position of the fracture EF is not known, that is the dimensions $x_1 l_x$, $x_2 l_x$, $x_3 l_x$, and $x_4 l_x$ are unknown. Consider fragment ABFE. Since the bottom reinforcement parallel to l_x is generally constant for the distance l_y , it exerts a moment $m_x l_y$ upon the fragment, and the reinforcement along the top

of the edge AB exerts a moment $m'_x l_y$. The total moment of the internal forces about AB is therefore $(m_x + m'_x)l_y$. If the intensity of the uniformly-distributed load on the slab is w , the total moment about AB of the load on the fragment is

$$[0.5x_1^2 l_y^2 - 0.33x_1^2 l_x (x_3 + x_4) l_y] w,$$

which must be equal to the total moment of the internal forces, that is

$$m_x + m'_x = \frac{w x_1^2 l_y^2}{6} [3 - 2(x_3 + x_4)] = C_1 w l_x^2. \quad (1)$$

Similarly, for fragment CDEF,

$$m_x + m''_x = \frac{w x_2^2 l_y^2}{6} [3 - 2(x_3 + x_4)] = C_2 w l_x^2. \quad (2)$$

For the triangular fragment ADE, equating the total moment of the internal forces $(m_y + m'_y)l_x$ to the moment of the load about AD, $\frac{w l_x x_3^2 l_y^2}{6}$, gives

$$m_y + m'_y = \frac{w x_3^2 l_y^2}{6} = K_1 w l_x^2. \quad (3)$$

Similarly, for fragment BCF, $m_y + m''_y = \frac{w x_4^2 l_y^2}{6} = K_2 w l_x^2. \quad (4)$

The coefficients in formulae (1) to (4) are

$$C_1 = \frac{x_1^2}{6} [3 - 2(x_3 + x_4)]; \quad C_2 = \frac{x_2^2}{6} [3 - 2(x_3 + x_4)]; \quad K_1 = \frac{x_3^2}{6}; \quad K_2 = \frac{x_4^2}{6}.$$

A chart giving values of C_1 and C_2 is given in Fig. 3. If a pattern of cracks is assumed, that is if values of the ratios x_1 to x_4 are assumed, the corresponding values of the coefficients and the value of $w l_x^2$ enable the sums of the bending moments to be calculated. The moments m'_x and m''_x at the supports occur only with the midspan moments m_x , and m'_y and m''_y only with m_y . The total resistance, therefore, remains unchanged if the bottom reinforcement is increased and the top reinforcement decreased, or inversely.

In the numerical examples which follow the method of designing slabs for various conditions is described, and in the first example a comparison is made with the results obtained by applying the recommendations of the British Standard Code of Practice No. 114.

EXAMPLE NO. 1.—The dimensions of a panel continuous over the supports on four sides are: l_x , 16.7 ft. and l_y , 17.8 ft.; $w = 350$ lb. per square foot. (a) Assume $x_1 = x_2 = 0.5$, and $x_3 = x_4 = 0.4$; therefore $x_3 + x_4 = 0.8$. Since

$$r = \frac{17.8}{16.7} = 1.06, \text{ from Fig. 3 } C_1 = C_2 = 0.0583. \text{ Therefore}$$

$m_x + m'_x = m_x + m''_x = 0.0583 w l_x^2 = 0.0583 \times 350 \times 16.7^2 = 5700$ ft.-lb. per foot. If the bending moment at the support is assumed to be 3200 ft.-lb., the bending moment at midspan is $5700 - 3200 = 2500$ ft.-lb. in the direction

of l_x . By substitution, $K_1 = K_2 = \frac{(1.06 \times 0.4^2)}{6} = 0.03$, and, from (3) and (4), $m_y + m'_y = m_y + m''_y = 0.03 \times 350 \times 16.7^2 = 2920$ ft.-lb. per foot. If the

bending moment at the support is assumed to be 1750 ft.-lb., the bending moment at midspan is $2920 - 1750 = 1170$ ft.-lb. in the direction of l_y . Thus all the bending moments required for the design are known. By symmetry, $x_1 = x_2 = 0.5$ is an accurate assumption, but $x_3 (= x_4)$ might be more or less than the assumed value of 0.4. Any other value assumed, as in (c), will affect the calculated bending moments, but, if the resistances required by any reasonable assumption are provided, the design will be sound. This view also applies to the division of the total bending moment between the sections at the supports and midspan. All bending moments are on 1-ft. width of slab.

(b) In accordance with the recommendations of British Standard Code No. 114, the bending moments in the foregoing are as follows:

$$m_x = 0.028 \times 350 \times 16.7^2 = 2740 \text{ ft.-lb.}; m'_x = m''_x = 0.037 \times 350 \times 16.7^2 = 3600 \text{ ft.-lb.}$$

$$m_y = 0.025 \times 350 \times 16.7^2 = 2440 \text{ ft.-lb.}; m'_y = m''_y = 0.033 \times 350 \times 16.7^2 = 3230 \text{ ft.-lb.}$$

These bending moments exceed those calculated by the proposed method, but resistance to them need be provided only on a width of slab equal to three-quarters of the span, whereas in the design based on the pattern of fractures it is assumed that the resistance is provided for the entire length and breadth of the panel.

(c) Assume $x_3 = x_4 = 0.2$, $x_3 + x_4 = 0.4$; then $m_x + m_x = m_x + m_x'' = 0.092wl_x^2$ compared with $0.0583wl_x^2$ in (a) and $(0.028 + 0.037) = 0.065wl_x^2$ in (b). Also,




Fig. 3.

$m_y + m_y' = m_y + m_y'' = 0.007wl_x^2$ compared with $0.030wl_x^2$ in (a) and $(0.025 + 0.033) = 0.058wl_x^2$ in (b).

EXAMPLE NO. 2.—Assume that the slab in Example No. 1 is freely supported along one of the shorter sides. Assume that $x_1 = x_2 = 0.5$, $x_3 = 0.35$, and $x_4 = 0.45$; $x_3 + x_4 = 0.8$ and $C_1 = C_2 = 0.0583$, and, as before, $m_x + m_x' = 5700$ ft.-lb. per foot, $m_x' = m_x''$, say, 3320 ft.-lb., and $m_x = 2380$ ft.-lb. Also, $K_1 = 0.023$, and $m_y + m_y' = 0.023 \times 350 \times 16.7^2 = 2250$ ft.-lb.; $K_2 = 0.038$, and $m_y + m_y'' = 0.038 \times 350 \times 16.7^2 = 3710$ ft.-lb. Since $m_y' = 0$, $m_y = 2250$ ft.-lb., and $m_y'' = 3710 - 2250 = 1460$ ft.-lb. per foot.

EXAMPLE NO. 3.—It is assumed that the reinforcement over the supports of the slab in Example No. 1 is such that $m_x' = 4410$ ft.-lb. and $m_x'' = 1770$ ft.-lb.

per foot. Therefore $\frac{m_x' - m_x''}{wl_x^2} = \frac{4410 - 1770}{350 \times 16.7^2} = 0.0272$. From (1) and (2),

$$\frac{m_x' - m_x''}{wl_x^2} = \frac{2l_x x_1 - l_x^2}{6l_x^2} [3 - 2(x_3 + x_4)]. \text{ If it is assumed that } x_3 = x_4 = 0.4,$$

from the two preceding equations $x_1 = 0.558$ and $x_2 = 0.442$, for which $C_1 = 0.073$ and $C_2 = 0.046$. Therefore $m_x + m_x' = 0.073 \times 350 \times 16.7^2 = 7100$ ft.-lb. and $m_x + m_x'' = 0.046 \times 350 \times 16.7^2 = 4450$ ft.-lb., from which $m_x = 7100 - 4410 = 2690$ ft.-lb., or $m_x = 4450 - 1770 = 2680$ ft.-lb. per foot.

Slab supported on Four Sides : Trapezoidal Load.

It is assumed that the intensity of load is constant in the direction l_y but varies from w_1 along AB to w_2 along CD (Fig. 2). The load can then be considered as a uniformly-distributed load w and a double triangularly-distributed load, the ordinate at CD being $w_2 - w$ (positive) and the ordinate at AB being $w - w_1$ (negative). The load w is the intensity of load at the fracture EF, and is therefore $0.5[w_1 + w_2 + (x_1 - x_2)w_0]$ if $w_0 = w_2 - w_1$. The action of w is similar to that described in the preceding part of this article. The action of the triangular loadings is considered in the following. The two actions must be superposed to obtain the resultant effect. Within limits, the values of x_1 to x_4 can be chosen freely as before, but the same pattern must be assumed for the two actions since they occur simultaneously.

It is seen that the maximum intensity of the negative load is $x_1 w_0$ and of the positive load $x_2 w_0$ as in Fig. 2. The load on an elementary strip a of fragment ABFE is $-(1 - y_1)[1 - y_1(x_3 + x_4)]x_1 w_0 l_y \cdot dy_1 (x_1 l_x)$, and the total moment about AB of the loads on all strips from $y_1 = 0$ to $y_1 = 1$ is $\frac{x_1^2 w_0 l_y^2 l_x}{12} [2 - (x_3 + x_4)]$,

which must equal the total moment of the internal forces, that is $(m_x + m_x')l_y$. Therefore

$$m_x + m_x' = -\frac{w_0 x_1^3 l_x^2}{12} [2 - (x_3 + x_4)] \quad (5)$$

$$\text{Similarly for fragment CDEF, } m_x + m_x'' = +\frac{w_0 x_2^3 l_x^2}{12} [2 - (x_3 + x_4)] \quad (6)$$

The load on an elementary strip b of fragment ADE is

$$-(1 - y_1)x_1^2x_3y_1w_0J_y dy_1$$

and, on strip c , $+(1 - y_2)x_2^2x_3y_2w_0J_y dy_2$. The total moment about AD on the loads on all strips b from $y_1 = 0$ to $y_1 = 1$ and on all strips c from $y_2 = 0$ to

$y_2 = 1$ is $\frac{x_3^2(x_2 - x_1)}{24}w_0J_y^2$, and must be equal to the total moment of the internal

forces $(m_y + m'_y)l_x$. Therefore

$$m_y + m'_y = \frac{x_3^2(x_2 - x_1)}{24}w_0J_y^2; \text{ and } m_y + m''_y = \frac{x_4^2(x_2 - x_1)}{24}w_0J_y^2 \quad (7) \text{ \& } (8)$$

EXAMPLE NO. 4.—Assume the data for a reinforced concrete retaining wall, freely supported along the two horizontal edges and continuous over the vertical edges, are: l_x (vertical), 13.1 ft.; l_y (horizontal), 16.4 ft.; w_1 , 102 lb. per square foot; w_2 , 410 lb. per square foot; therefore $w_0 = 410 - 102 = 308$ lb. per square foot, and $w = 0.5[102 + 410 + (0.55 - 0.45)308] = 272$ lb. per square foot.

Assume $x_1 = 0.55$, $x_2 = 0.45$, and $x_3 = x_4 = 0.4$. Due to w , by calculations as in the first part of this article, $m_x + m'_x = 3430$ ft.-lb., $m_x + m''_x = 2200$ ft.-lb., and $m_y + m'_y = m_y + m''_y = 2010$ ft.-lb. per foot. Due to w_0 , from formula (5),

$$m_x + m'_x = -0.55^3(2 - 0.8)308 \times \frac{13.1^2}{12} = -880 \text{ ft.-lb.}; \text{ from formula (6),}$$

$$m_x + m''_x = +0.45^3 \times 1.2 \times 308 \times \frac{13.1^2}{12} = +485 \text{ ft.-lb.}; \text{ from formulae (7)}$$

$$\text{and (8), } m_y + m'_y = m_y + m''_y = 0.4^2(0.45 - 0.55)308 \times \frac{16.4^2}{24} = -55 \text{ ft.-lb.}$$

By addition, and since $m'_x = m''_x = 0$, $m_x = 3430 - 880 = 2550$ ft.-lb., or $m_x = 2200 + 485 = 2685$ ft.-lb.; the average of these two values is sufficiently correct for design purposes, that is $m_x = 2620$ ft.-lb. Also by addition, $m_y + m'_y = m_y + m''_y = 2010 - 55 = 1955$ ft.-lb. and, assuming $m'_y = m''_y$, say, 860 ft.-lb., $m_y = 1955 - 860 = 1095$ ft.-lb. per foot.

Slab supported on Three Sides: Triangularly-distributed Load.

The common case of a slab, such as the wall of a container, continuous at the bottom edge and at the two vertical edges but unsupported along the top edge, is considered in the following. The intensity of the load is assumed to vary from nothing at the top to w at the bottom. The notation is generally as in the preceding analyses and as in Figs. 4 and 5.

CASE I.— $l_y > l_x$ (Fig. 4).—The lines of probable fracture are DG and CH. The load dP_1 on an elementary strip of the fragment CDGH is $(1 - 2x_3 + 2x_3y)w_0J_y dy$, and on an elementary strip of the fragment ADG the load dP_2 is $(1 - y)x_3w_0J_y dy$. If unit displacement at right-angles to the plane of the slab is applied to the edge GH, the fragments remaining plane, the movement of dP_1 is $1 - y$ unit, and the movement of the centroid of dP_2 is $0.5(1 - y)$ unit. The work done by the load on the strip of length l_y is $(1 - y)(dP_1 + dP_2)$,

that is $(1-y)(1-x_3+x_3y)ywl_y l_x dy$. By integration from $y=0$ to $y=1$, the total work A_e done by the external forces is $\frac{2-x_3}{12}wl_y l_x$. The total moment of the internal forces on the fragment CDGH is $2m_x x_3 l_y + m'_x l_y$. Since the angle of rotation of the fragment is $\frac{1}{l_x}$, the work done A_1 by the internal forces is $(m'_x + 2x_3 m_x)r$. Similarly, for the fragments ADG and BCH, the total moment of the internal forces about the vertical edges is $[(m_y + m'_y) + (m_y + m''_y)]l_x$, the




Fig. 4.




Fig. 5.

angle is $\frac{1}{x_3 l_y}$, and the work done A_2 is $\frac{2}{x_3 r}(m_y + m'_y)$. The total work A_i done by the internal forces is $A_1 + A_2$. Since $A_i = A_e$

$$(2-x_3)wl_y l_x = 12(m'_x + 2x_3 m_x)r + \frac{24(m_y + m''_y)}{x_3 r} \quad (9)$$

Another equation, which results from the fact that the value of x_3 must be such that the load carrying capacity of the slab is a minimum (that is $\frac{dw}{dx_3} = 0$), is

$$4(1-x_3)(m_y + m'_y) = x_3^2 r^2 (4m_x + m''_x) \quad (10)$$

If $u_x = \frac{m_x}{wl_x^2}$, $u_1 = \frac{m'_x}{wl_x^2}$, $u_y = \frac{m_y}{wl_y^2}$, and $u_2 = \frac{m'_y}{wl_y^2}$, from (9) and (10)

$$u_1 = \frac{1}{6} - \frac{4}{x_3}(u_y + u_2) \text{ and } u_x = -\frac{1}{24} + \frac{1}{x_3^2}(u_y + u_2) \quad (11)$$

The value of x_3 is assumed and also positive values of any two of the coefficients u_y , u_2 , u_1 , and u_x except u_1 and u_x together. Substitution in (11) gives the values of the other two coefficients.

EXAMPLE No. 5.—The data for a slab supported on three sides are l_y , 13.1 ft.; l_x , 9.8 ft.; w , 308 lb. per square foot. Assume $x_3 = 0.3$, $u_1 = 0.07$, and

$u_y = 0.005$; from the first of formulæ (11), $u_2 = 0.0023$. Substituting in the second formula (11), $u_x = 0.0393$. Therefore the bending moments are:

$m_x = 0.0393 \times 308 \times 9.8^2 = 1160$ ft.-lb.; $m'_x = 0.07 \times 308 \times 9.8^2 = 2060$ ft.-lb.
 $m_y = 0.005 \times 308 \times 13.1^2 = 265$ ft.-lb.; $m'_y = 0.0023 \times 308 \times 13.1^2 = 120$ ft.-lb. per foot.

CASE II.— $l_y < l_x$ (Fig. 5).—The lines of probable fractures are DK, CK, and KJ. By a method of analysis similar to the foregoing, the equation expressing the equality of internal and external work is

$$24(u_x + u_1) + 96x_2(u_y + u_2) - 6x_2 + 4x_2^2 - x_2^3 = f(x_2) = 0, \quad (12)$$

and from $\frac{df(x_2)}{dx_2} = 0$, $u_y + u_2 = \frac{6 - 8x_2 + 3x_2^2}{96}$ (13)

Combining (12) and (13), $u_x + u_1 = \frac{x_2^2(2 - x_2)}{12}$ (14)

EXAMPLE NO. 6.—The data for a slab supported on three sides are: l_y , 9.8 ft.; l_x , 16.4 ft.; and $w = 510$ lb. per square foot. Assume $x_2 = 0.5$, $u_y = u_2$, and $u'_x = 0.5u_1$. Therefore $u_x + u_1 = 0.031$ from (14), and $u_x = 0.0103$ and $u_1 = 0.0207$; $u_y + u_2 = 0.025$ from (13), and $u_y = u_2 = 0.0125$. Therefore the bending moments are:

$$m_x = 0.0103 \times 510 \times 16.4^2 = 1420 \text{ ft.-lb.}; m'_x = 0.0207 \times 510 \times 16.4^2 = 2850 \text{ ft.-lb. per foot.}$$

$$m_y = m'_y = m''_y = 0.0125 \times 510 \times 9.8^2 = 610 \text{ ft.-lb. per foot.}$$

Effect of the Wind on Golden Gate Bridge.

As a result of damage to the Golden Gate bridge at San Francisco, an investigation is to be made on the question of whether the bridge can be strengthened. The bridge is a suspended steel span of 4,200 ft. During a gale in December, when the wind exceeded 50 miles an hour continuously for four hours and reached a maximum of 60 miles an hour, the maximum vertical vibration of the deck was 130-in. double amplitude with a frequency of 8.4 cycles per minute. This occurred at a quarter point, indicating unsymmetrical move-

ment. No conclusions could be reached whether or not there was torsional motion, but eye-witness reports say there was. (It was an unsymmetrical torsional movement caused by the wind that led to the failure of the Tacoma Narrows bridge in 1940.) This was the greatest movement of the bridge that has been recorded. The bridge has been subjected to winds of greater velocity, but none was of such long duration or in a direction to cause such a large movement according to the records of the structure.

Dams in India.

THE Government of the Punjab has engaged Mr. Harvey Slocum, who was the construction superintendent of the Grand Coulee, Friant, Bull Shoals, and other large dams in the United States of America, to supervise the construction of dams in the State. Up to fifty American engineers will accompany Mr. Slocum. The largest dam now in course of con-

struction in the Punjab is the Bhakra dam, which will be 680 ft. high and contain five million cubic yards of concrete. Several other dams are in course of construction or are projected in the Punjab, and it is understood that American engineers are being employed because of the slow rate of progress at present being made.

Book Reviews.

"Reinforced Concrete." By Oscar Faber, C.B.E.
(London: E. & F. N. Spon, Ltd. Price 30s.)

THIS book of 228 pages is written in a most interesting manner suited in particular to the novice but it will also be beneficial to experienced engineers. It deals with the subject with particular reference to the British Standard Code of Practice No. 114.

The first chapter traces the properties and uses of concrete from its inception as a structural material and the second deals with progress in recent years, including prestressed concrete. The next two chapters describe the materials of which reinforced concrete is composed as well as their physical characteristics, both separately and in combination, and give valuable information on water-cement ratio, shrinkage, and cube and cylinder strengths. The elementary design of slabs, beams, columns, and footings is clearly dealt with in chapters 5 to 10. Chapters 11 to 17 deal with special applications and structures such as piles, silos, shell roofs, reservoirs, chimneys, precast concrete, and prestressed concrete. These chapters, though short, contain much good information.

The book, in its brief treatment of all these subjects, avoids the use of higher mathematics. In the second chapter attention is drawn to the possible objections to the use in ordinary reinforced concrete of high steel stresses such as 27,000 lb. per square inch and above. The examples of columns, particularly on page 138, illustrate the practical difficulties that occur as the amount of longitudinal reinforcement approaches the 8 per cent. upper limit permitted by the code. The book contains within its short limits much useful information, with many tables and graphs, and is highly recommended.

R. P. M.

"Des Ingenieurs Taschenbuch." Volume III.
Bauingenieurwesen. Part 3. (Berlin: Wilhelm Ernst & Sohn. 1951. Price 15 DM.)

THE 27th edition of this handbook deals with foundations and earthworks; water-

ways; dams and hydro-electric works; and water supply, sewerage, and sewage disposal. The basic problems and theories are stated concisely, and there are many excellent illustrations and copious references. Foundations in ground and under water are described in great detail. Data are given for any combination of surcharge against retaining walls, with diagrams relating to retaining walls, quay walls, and abutments. Foundations for machines are discussed, with special reference to preventing vibration. Equations are given for determining economical haulage distances in tunnels. In the section on waterways are discussed hydrological principles, planning and design of canals, channels, river improvements, estuaries and tidal work, docks and harbours, and land drainage. Considerable attention is given to the design of dams of the arch type and the economics of hydro-electric works. The notes on the disposal of storm-water are interesting insofar as empirical formulae still appear to be used, whereas in this country such calculations are based on the Lloyd-Davies method of 1906 with improvements such as the time-area graph.

"The Structural Analysis of the Dome of Discovery."
By T. O. Lazarides. (London: Crosby Lockwood & Son, Ltd. Price 25s.)

THE original design of the Dome of Discovery at the Festival of Britain was an approximate treatment. An exact analysis was, however, later carried out by the method of relaxation for statically indeterminate structures as described by Professor R. V. Southwell. The author gives a complete description of the method and details of the calculations, including the loading assumptions, the choice of the axes, the calculation of the influence coefficients, the preparation of the conversion, operational and main relaxation tables, and the recompounding of the individual members. A full discussion of the behaviour of the structure under load completes this record of redundant space-frame calculation.

The Pathology of Reinforced Concrete.

By HENRY LOSSIER.

THE following is an abstract of a book entitled "La Pathologie du Béton Armé," written by M. Henry Lossier, the eminent French engineer, and published by Editions Dunod, of Paris, which is translated here by arrangement with the author and publisher. In this abstract, which will be continued in later numbers of this journal, M. Lossier gives much valuable information based on his long experience. The translation from the French is by Mr. R. E. Walsh, M.A., B.Sc.

CHOICE OF TYPE OF STRUCTURE.

Curved Beams, or "Flat Arches".

A special case is the flat "arch", that is a beam with a straight extrados and a slightly arched intrados. The design of these beams was the subject several years ago of many discussions; some engineers treated them as fixed-ended beams of variable section and others as true arches subjected to horizontal thrust. This distinction is, if not theoretically at least practically, of no moment. If it is assumed that the deflection of the intrados is comparatively great, and if the stresses are computed on the basis of an elastic arch fixed at its ends—that is to say, assuming that the supports can resist a horizontal thrust without deforming—a line of thrust inclined towards the supports may be drawn approximately as shown in Fig. 1. As the deflection of the intrados diminishes the thrusts R become more nearly vertical and the horizontal




Fig. 1.



Fig. 2.

thrust diminishes. On reaching the limiting case of zero deflection, the two thrusts are then wholly vertical and there is no horizontal thrust. There is thus no sudden change from the functioning as an arch to the functioning as a beam. In the case of very flat members used in structures of this kind, the results of the two methods differ only slightly.

The foregoing naturally assumes a normally reinforced member. If, as has sometimes happened, the reinforcement is incapable of resisting the imposed bending moments, the beam functions in the manner represented by Fig. 2. At first it behaves as an arch with fixed ends and is subjected to large bending moments at the supports and at mid-span; but these sections, being insufficiently reinforced, crack and the member opens in the extrados at the supports and in the intrados at mid-span. As a consequence of this self-adjustment, the member becomes a true arch which either stands or falls depending on whether or not the supports are capable of resisting the horizontal thrust without yielding. Since it is exceptional for the supports to be capable of resisting large horizontal thrusts without yielding, it is generally prudent to regard spans of this kind as beams of variable section with ends either fixed or freely supported according to the conditions.

Series of Arches.

A series of arches of equal span without tie-bars, with walls or rocker bearings as intermediate supports, and capable of resisting only purely vertical forces, was the cause of one of the worst accidents recorded in the history of reinforced concrete. Arches of this kind, which had to

carry a load of earth filling, were used to roof a large reservoir. Each span had been calculated as an arch on the assumption that, as the spans were identical and equally loaded, the horizontal thrusts would balance one another at each intermediate support. On covering the roof, instead of spreading the filling uniformly over all the spans, the earth was placed on a few spans only. The horizontal thrust from the loaded vaults, not being balanced by that of the neighbouring unloaded ones, caused the former to flatten with accompanying complete collapse of the whole structure as represented in Fig. 3.

In order that multiple vaults of this kind should be stable, they must comply with the two conditions depicted in Fig. 4: first, the outer supports A and B must resist without yielding the inclined thrust R , and secondly the load must be uniformly applied over all the vaults.

Generally, accidents of this nature are attributable to one of two causes, namely, the designer is content to provide ties in the outer spans, without bothering about the strength and rigidity of the end supports; or the loads on the different spans are not kept equal. When a series of vaults must support variable loads the stresses can be determined with precision by the method of analysing a continuous elastic arch. When structures of little importance, which do not justify such an exact analysis, are concerned, it is sufficient to consider each span as an arch with fixed supports under the action of the dead load, and as a continuous beam, integral with its piers, under the action of the live load.




Fig. 3.




Fig. 4.

Continuous Beams.

Some engineers think that continuous beams should be designed as homogeneous beams, that is according to the common formulæ based on the elastic theory. Others consider that they should be designed by special empirical methods, assuming only partial continuity. Beams designed and constructed for perfect continuity exhibit, in general, the advantage of cracking less than those designed for partial continuity. In effect, because the reinforcement is designed to resist tensile forces both at the supports and at intermediate sections, the limits of fatigue normal to the steel and the concrete are not exceeded anywhere, unless it be to an insignificant extent.

Partially-continuous beams have often been designed by adopting the simple

formula $\frac{wl^2}{10}$ for the bending moment between the supports, half only of the bars being bent-up over the supports. Under the action of the dead load, the stresses in sections over the intermediate supports tend to be higher than those for which the reinforcement is designed. Due to the resulting excessive deformation the distribution of the bending moments adjusts itself, the sections at the supports which are too weak relaxing at the expense of the stronger sections between the supports. There is then formed (sometimes at the cost of cracking of the extrados over the supports) a new state of equilibrium which tends to approach automatically the original hypothesis without any real sacrifice of safety. The facility possessed by statically indeterminate structures (as also, moreover, by living organisms) of adapting themselves to abnormal conditions, with the object of delaying as much as possible the moment of their dissolution, is an almost universal phenomenon.

In practice, a beam designed with monolithic spans on the assumption of partial continuity does not represent, in principle, a pathological case, provided that (a) the relative weakness of the sections over the supports is compensated by a corresponding excess of strength in the intermediate sections, and (b) the difference between the allowable values for the moments and those considered as limiting remains within the range usually




Fig. 5.

accepted. A few cracks causing no risk to the stability of the structure are normally the only objection to this departure from the common theory.

Arches and Vaults.

The arch bridge is a type widely built in reinforced concrete because it is in general the most economical.

The adoption of a hingeless hyperstatic arch, when the abutments are not absolutely rigid, is always an erroneous conception. It is, however, only seldom that a true failure occurs, since the arch forms its own hinges on cracking, but more or less serious damage may be caused. The use of temporary hinges or of lowering the centering by jacks is only a partial remedy, because eventual shrinkage and settlement of the abutments can some-

times continue for several years before they become quite stable. One of the most typical cases is a footbridge of 140-ft. span, built over a canal in the year 1931 (Fig. 5). This bridge was founded on gently-raking piles bearing on rock underlying mud of no consistency. The inclination of the thrust R of the bridge not coinciding with that of the piles, and the resistance of the mud being incapable of preventing movement of the piles, the abutments spread, following the removal of the centering of the arch, with increasing rapidity leading to the complete collapse of the bridge within six days. It is essential in such cases either to construct the foundations of stable monolithic material or to provide abutments of piles having varying slopes according to the thrusts of the arch as generated by all possible combinations of loading.

CALCULATIONS OF STRENGTH.

Theory and Reality.

It is possible to be at one and the same time an outstanding mathematician and a mediocre engineer, for in engineering, as in many other arts, pure science is of little avail unless it is directed by sound common sense. Two principal considerations must be borne in mind: First reality, which is independent of any ideology or preconceptions; Secondly theory, which

is of human origin and of arbitrary character, which seeks to impart a simplified and comprehensible image of reality, enabling reasoning and the formulation of conclusions to be made with the least risk of error. No theory coincides exactly with reality, and their divergencies are the principal cause of most of the false reasoning of theorists. Who has not, in identifying an approximate image (which is the theory) with the object itself (which is the reality), followed indefinitely the thread of his reasoning oblivious of the fact that he has long before left the track of healthy logic? In metal construction the working of most structures depends on a smaller number of factors than does reinforced concrete structures, because the latter are subjected to the factors of monolithism and variations with the weather of the characteristics of some of their components. This is why builders in reinforced concrete are particularly exposed to the vices of impenitent theorists.




Fig. 6.

SLAB-AND-BEAM CONSTRUCTION.—Consider as an example the case of a simple slab with parallel and equidistant beams (Fig. 6). In designing this slab the common formulæ applicable to a continuous beam of uniform section resting freely on unyielding supports are most frequently used. Yet (a) the slab is not of uniform section since it has two layers of reinforcement over the beams and a single layer between them; (b) the slab does not rest freely on its supports since it is integral with the beams which resist the torsion; and (c) the supports of the slab are not unyielding since the beams deflect unequally under the action of the varying live loads; this deflection diminishes towards the ends. The striking differences which exist between the assumptions made by designers and the reality in this reputedly simple case demonstrate how illusory may be the results of some accepted methods of calculation.

BOW-STRING BRIDGES.—As a second example, consider the case of a bow-string bridge (Fig. 7) comprising a lightly-reinforced concrete arch and a horizontal tension member having a high percentage of reinforcement. In course of time the shrinkage and creep of the concrete have a much greater effect on the linear variations of the arch than on those of the tie. Also the functioning of the structure will change, under both the live and dead loads, after its completion, and for important bridges an attempt should be made to evaluate the extent of these changes.

MULTIPLE-SPAN BRIDGES.—Arch bridges comprising multiple spans have also suffered from bad theory. In the early days of my career I designed a reinforced concrete viaduct with arches of equal span carried on high piers. Using the theory of an elastic ellipse I took into account the deformation of both piers and arches due to accidental loads. Compared with the approximate method, based on the assumption of a series of arches on fixed supports in every case, this method, undoubtedly more exacting, led logically to a thickening of the arches and a thinning of the piers. This design was submitted in a competition, and the assessor was fiercely opposed to what he called a heresy. After a demonstration of principle with a model made of easily deformable material, he asserted that he would never agree that a test on a model




Fig. 7.

could challenge a method he had taught for many years.

THE MODULAR RATIO.—The coefficient m , by which the area of steel must be multiplied to make it equivalent to the area of concrete, has been the subject of much controversy. There were originally two opposing doctrines. Hennebique proposed an arbitrary compressive working stress in the concrete of 355 lb. per square inch and of 17,000 lb. per square inch in the steel, thus giving on m a value of 48. The orthodox school, starting with the premise that concrete has a mean coefficient of elasticity of about one-tenth of that of steel, decided that $m = 10$, and this value was adopted in many regulations. If this value has on occasions led to some needless extravagance in reinforcement, it has never been the cause of a failure.

Later, in order to take into account several factors, and in particular the effect of the concrete in tension on the position of the neutral axis in members subjected to bending, a modular ratio of 15 was adopted without regard to the formula derived from actual tests by M. Caquot and which logically incorporated the percentage of reinforcement. This constant value of 15 is much used in current practice, but I have often wondered why so many engineers have such an affection for the modular ratio. Let us follow the normal history of a compression member in service. At the outset of its life it will probably act as though the steel were equivalent to the concrete, but with its

section multiplied by $m = \frac{E_s}{E_c} E_s$ and E_c

being the respective coefficients of elasticity of the two materials. Then, under the combined effect of shrinkage during hardening and creep, the concrete, by gradually shortening, will free itself partially from its initial restraint, thereby transferring load to the steel which has not shortened. In other words, the coefficient m will pass from a value ranging from 7 to 10 to a value which might exceed in certain cases three times these values.

It appears to be illogical to use a fixed

value of m which can agree only for the time being with reality, and which affects the cost of construction only very slightly except in the case of compression reinforcement, the use of which is gradually being abandoned. Let a modular ratio of 10, 15, or even 20 be used, but do not let an academic viewpoint prevail when it is not in accordance with reality.

STRENGTH OF CONCRETE.—A few words on the theoretical exactness of calculations of the strength of concrete. There are some who persist in working to an imposing number of decimal places, although the practical agreement between the theories and reality is not greater than 70 per cent. to 80 per cent. There are others who, with greater justification, repose unlimited confidence in calculations based on the mathematical theory of elasticity. Again, basic hypotheses may differ very greatly from reality. On the one hand reinforced concrete is not in every respect a homogeneous material, and on the other hand the errors of the hypotheses are multiplied along with the

normal factors. In short, the functioning of reinforced concrete structures can seldom be defined theoretically with great exactitude even by the most orthodox calculations of strength.

Hennibique carried out a number of works by applying a method sometimes considered, not without reason, to be heretical since it leads to the equating of an external bending moment with a moment of resistance formed by two forces, one tensile and the other compressive, which are not equal. Nevertheless no failure has occurred as a result of the use of this method, thanks to the sound common sense of its author and, it must be admitted, to the phenomenon of adaptation which compensates in some cases for the designer's errors. An engineer worthy of the name ought to have sufficient mathematical knowledge to enable him to comprehend all the current theoretical difficulties; but this knowledge will be of little value unless he possesses, in addition, the rare quality of common sense.

(To be continued.)

Precast Concrete Wall Slabs.

As the result of experience of the use of precast concrete insulated wall slabs on a power station building, on which 60,000 sq. ft. of such panels were erected a year previously, the slab shown in Figs. 1 and 2

has been adopted by the Union Carbide and Carbon Corporation of the U.S.A. for 500,000 sq. ft. of walls at a new plant at Marietta, Ohio.

The area of the slabs, which are in two sizes measuring 8 ft. by 8 ft. and 8 ft. by 10 ft., is a compromise between the desire to have as few joints as possible and ease of handling the slabs. The height of the slabs also conforms to the window heights and other features of the elevations.

The slabs are 5 in. thick, and comprise two outer layers of concrete $1\frac{1}{2}$ in. thick and a core of insulating material $1\frac{1}{2}$ in. thick. The concrete has a compressive strength at 28 days of 4000 lb. per square inch, and comprises aggregate of $\frac{3}{4}$ in. maximum size and 560 lb. of high-early-strength Portland cement per cubic yard. Each layer of concrete is reinforced with 4-in. square mesh supplied in flat sheets. The two layers of concrete are joined by strips of expanded metal bent channel shape, as shown in the section in Fig. 1. Two U-shape bars project from the top




Fig. 1.

of the slab for use as lifting hooks, and threaded inserts to receive connecting bolts are embedded near the top and bottom of each slab.

As 3000 sq. ft. of slabs are being made daily, four different insulating materials are used in order to be sure of continuity of supply. These are (1) precast wood-

and after the slabs are erected the joints are packed with oakum and caulked. The edges are slightly bevelled to reduce damage to the arrises, and also to make less noticeable any slight irregularities.

The slabs are made in steel moulds. The inner face has a matt finish produced by using muslin in the bottom of the




Fig. 2.

wool slabs, (2) precast slabs made with wood chips, (3) cellular glass, and (4) glass-fibre. These are supplied in sheets 2 ft. wide by 8 ft. long. The coefficient of heat transfer of these materials ranges from 0.14 to 0.33 B.Th.U. per hour per square foot per degree Fahr., compared with 0.36 for a 12-in. brick wall.

Tongue-and-groove joints are formed on all four edges. Before the slabs are erected a continuous strip of impervious cellular rubber is cemented in the grooves,

mould. The outer face is finished with a wooden float and brushed to produce uneven shallow grooves vertically.

At every third course the slabs are supported on the steel frame of the building by means of clips as shown in Fig. 2. The slabs are hoisted by a crane, and 2000 sq. ft. are normally erected in an 8-hour day by a foreman and ten men. The foregoing notes and the illustrations are from "Engineering News-Record" for January 24, 1952.

Analysis of Groups of Piles.

A Semi-Graphical Method Based upon Displacements.

By R. J. WILKINS, M.Sc.(Eng.), A.M.Inst.C.E., M.I.Struct.E.

THE January, 1952, number of "Concrete and Constructional Engineering" contained an article by Mr. G. P. Manning on the analysis of groups of piles by the displacement method in which a general treatment was developed for the case of two inclined piles joined at the apex. This problem lends itself to a convenient semi-graphical method which may be applied directly to any numerical case and which forms an interesting extension of the methods previously described.




Fig. 1.




Fig. 2.

No new theoretical treatment is involved by the semi-graphical method, which is based on the common methods used in moment-distribution analyses for the determination of secondary bending moments in framed girders with rigid joints. For comparison, the numerical examples used in Mr. Manning's article are used to illustrate the method, and the same notation is employed. The selection of any particular method of structural analysis is largely a matter of personal preference, and claims of superiority must be carefully assessed. The present method may appeal to some designers because of its numerical and graphical basis.

Fig. 1 shows two identical raking piles subjected to a horizontal pull of 15 tons. As pointed out by Mr. Manning, such piles are usually designed as pin-jointed at both ends as in Fig. 1b, although actually they may be monolithic with the super-

structure at the apex B and approach fixed-end conditions at A and C as shown in Fig. 1c. Considering the pin-jointed structure in Fig. 2a, the forces in the piles will be 23.7 tons direct tension in pile AB and direct compression in pile BC. The piles have a slope of three vertically to one horizontally. These forces will cause axial changes of length of $\frac{694}{E}$ in each case. A Williot displacement diagram

may now be drawn for the pin-jointed structure as in Fig. 2b, in which ab' represents to scale the lengthening of AB, and cb' the shortening of BC. Lines drawn normal to the direction of the axial changes in length represent the arcs of rotation about A and C and enable the displaced position of B to be determined from the intersection of the lines. Fig. 3a shows the displaced position of the fixed-ended




Fig. 3.

structure in which the members AB' and $B'C$ are considered to be held by external restraining moments in such a manner that the tangents at the extremities are parallel to the original position of the member but displaced from it by a relative displacement Δ . The value of this displacement may be scaled from the displacement diagram as $\frac{2082}{E}$.

When a member of uniform EI is fixed at its ends and these ends are then displaced a relative distance Δ , but remain parallel, then moments are produced at each end of the member of magnitude $\frac{6EI\Delta}{h^2}$. The proof of this formula is given in text-books; it is one of the basic formulæ in moment-distribution methods. Fig. 3b shows how the formula is derived from the moment-area properties of the elastic curve. Substitution of $\frac{2082}{E}$ for Δ , and the values for I and h , give the fixing moment at each end of AB and BC as 32,400 in.-lb. while the members are externally restrained in position. Note that a numerical value of E is not required since it cancels out upon substitution of Δ .

In the actual structure, for the conditions shown joint B is free to rotate




Fig. 4.

and no external moment is applied at this joint. Fig. 3 shows the moment-distribution table for the one operation of releasing joint B and giving the final moment $M_A = M_C = 16,200$ in.-lb. as previously obtained. Fig. 4 shows the semi-graphical method applied to the same structure when subjected to a vertical load of 60 tons applied at B. In this case no balancing operation is required, and $M_A = M_B = M_C = 4800$ in.-lb. as before. The unbalanced shearing forces which arise from this method are very small and may be neglected. Cases of unsymmetrical piles, different end conditions, and so on, may be allowed for by the common methods of moment distribution when extending the analysis to other cases.

The valuable comments made by Mr. Manning on the effect of ground conditions, the effective length of the pile, and the influence of hard layers near ground level remain valid, since the assumptions made for a particular design depend upon engineering judgment and in themselves are just as important as the structural analysis. They are clearly independent of the particular method employed for a structural solution.

A Bridge-testing Machine.

A VEHICLE weighing 85 tons for testing the strength of road bridges has been completed for the Ministry of Transport. The main feature of the machine is a slab of concrete 35 ft. long by 7 ft. 9 in. wide by 3 ft. thick and weighing 50 tons. This slab is mounted on rails on a solid-tyred well-deck trailer in such a manner that it can be rolled along until nearly half its

length overhangs the end of the trailer. A further load of 30 tons of ballast can be piled into a well at the top of the slab, and the weight on one bogey can be varied from 20 to 90 tons. Tests on road bridges were to begin in June. The machine is to be used mainly to test the ability of masonry arch bridges to carry heavy loads.

A Precast Reinforced Concrete Dome.

THE construction with precast reinforced concrete segments of a dome of 100 ft. diameter in a church recently rebuilt in Karlsruhe is described in a recent number of "Beton-und Stahlbetonbau." The dome comprises sixty-four identical segments, the bases of which are supported on a tension ring on masonry walls, and the tops against a thrust ring which also supports a skylight. Provision is made for a false domed ceiling to be attached later. Timber scaffolding (*Fig. 2*) erected to support the thrust ring also supported the pivot of a rotating gantry crane (*Fig. 3*), the other support of which was

this temporary condition the tensile stress in the reinforcement was 28,500 lb. per square inch.

The segments are tee-shape, the thickness of the flanges being 2 in. They are of dense concrete, so it was not considered necessary to provide a waterproof covering except at the cornice. At the abutting edges of the segments the thickness of the flanges is 4 in. and a watertight joint is formed by a covering of semi-circular concrete tiles. The ribs of the segments are 16 in. deep and taper generally from 4 in. at the bottom to about 7 in. at the junction with the flange,




Fig. 1.—Mould for Making Segments.

a bogie on a rail on the tension ring. The segments were cast on the ground floor of the structure (*Fig. 1*) and placed in position by the crane. To avoid unbalanced thrusts on the thrust ring during construction, the segments were erected in pairs opposite one another (*Fig. 2*). When all the segments had been erected, the joints in the thrust and tension rings were filled with concrete.

The segments act as curved ribs, there being no circumferential stresses owing to the joints between the segments. Circumferential forces are resisted entirely by the thrust and tension rings. Under the most unfavourable loads, the stresses in the segments are almost entirely compressive. Only during erection were the segments subjected to large bending stresses, when they had to support their own weight and resist wind forces while acting as freely-supported beams. In

thus permitting easy removal from the moulds. The radius of the segments is about 61 ft.

The curved parts of the moulds (*Fig. 1*) were faced with concrete. A rough mould was made first from old bricks and masonry and then finished accurately with reinforced concrete. Three moulds were employed, each being used more than twenty times. No special measures were used to accelerate the hardening of the concrete. The concrete surfaces of the mould formed a smooth finish on the segments. After being lifted vertically from the mould each segment, which weighed about 4 tons, was turned lengthwise and hoisted obliquely, and for this operation two hand-winches were used in conjunction with the crane. The total weight of the reinforced concrete dome is much less than the weight of the former wooden dome.



Fig. 2.




Fig. 3.

Mobile Concreting Plant.

THE illustrations show the method of concreting channels on the main road near Doncaster by the use of a mobile plant. The work was done for the West Riding of Yorkshire County Council under the direction of Mr. C. Maynard Lovell, O.B.E., County Engineer.

The mixing plant consisted of a weigh-batcher, a high-lift loading shovel, and two 10/7 concrete mixers. The latter

were raised to discharge directly into the lorries. Three lorries (*Fig. 1*) were provided with an opening in the side; this was fitted with a sliding door on the inside of the lorry and a detachable chute was made to enable the concrete to be placed directly into position.

The channel was provided with a thin surface course of white concrete. To mix and place this material a mobile plant



Fig. 1.—Concreting Road Channel.




Fig. 2.—Mixing Plant for Surface Concrete.

mounted on a 5-ton low-loader trailer (Fig. 2) was set up consisting of storage hoppers for $\frac{3}{4}$ -in. aggregate and limestone dust with controlled outlet chutes, and a $5/3\frac{1}{2}$ concrete mixer discharging into a hopper provided with a chute to a controlled discharge outlet. The trailer was towed by a lorry carrying a water-

storage tank from which water was fed by gravity to the mixer. White Portland cement for the topping was also carried in the lorry.

By the use of these lorries, the mobile mixing plant, and a mechanical ditcher for excavation, a maximum output of 450 linear yards per day was obtained.

The Reinforced Concrete Association.

THE supply of reinforcement bars was the main topic discussed at the annual luncheon of the Reinforced Concrete Association held in London last month.

Mr. J. Cuerel (the President) said that, although the Government was convinced that reinforced concrete was a steel saver rather than a steel user, the supply of reinforcement bars was not sufficient for requirements. In the year 1950 the consumption of reinforcement bars was 200,000 tons, in 1951 it was 240,000 tons, and for the months of 1952 for which figures were available the consumption was at the rate of only 200,000 tons a year, of which about one-quarter was imported. The consumption of reinforcement bars was the criterion of the progress of reinforced concrete, and it was obvious that the allocation of steel for reinforcement bars was insufficient for the nation's needs. In the United States of America the consumption of reinforcement bars per head of population was twice as much as in Great Britain. The present scarcity resulted in designing to suit the sizes of bars available, work was delayed because the contractor had to wait for bars to be delivered, and men did not work well if they did not know when the next supply of bars would arrive. The speaker pleaded for a larger allocation of reinforcement bars so that full advantage could be taken of the economy in steel that resulted from the use of reinforced concrete. There was now a better supply of wire for prestressed concrete.

The President mentioned that the Association was increasing its membership, and that it was influential in the preparation of codes of practice, by-laws, and other regulations relating to reinforced concrete. The Association was considering the formation of a new class of membership for works supervisors and men in similar positions.

The Minister of Works (The Rt. Hon. David Eccles, M.P.) said that he was convinced of the great economy of steel made possible by the use of reinforced and prestressed concrete, and had instructed his Ministry to use these materials wherever possible. He was also urging the Ministry of Supply to make available larger quantities of bars and wire. As soon as circumstances permitted he would abolish as many as possible of the present restrictions and duties of the Ministry of Works, so that the industry could again manage its own affairs.

The Council for the ensuing year is as follows: President, Mr. M. G. Cowlishaw (Guest, Keen & Nettlefolds (South Wales), Ltd.).

Vice-President, Mr. H. G. Cousins.

Members: Messrs. E. Bellringer (Stothert & Pitt, Ltd.), E. J. Cook (Richard Costain, Ltd.), E. L. V. Dakin, M.C. (Wilson Lovatt & Sons, Ltd.), E. R. Hole (Holland & Hannen and Cubitts, Ltd.), C. H. S. Howkins, O.B.E. (Howard Farrow, Ltd.), W. K. Laing, M.A. (John Laing & Son, Ltd.), L. J. Murdock, Ph.D., M.Sc. (George Wimpey & Co., Ltd.), H. F. Rosevear (Sir Robert McAlpine & Sons, Ltd.), E. S. Shellard (Associated Portland Cement Manufacturers, Ltd.), H. E. Steinberg (Considere Constructions, Ltd.), G. W. Stokes (Matthews & Mumby, Ltd.), F. W. Sully (Holloway Bros. (London), Ltd.), J. W. Vanderbeeck (British Reinforced Concrete Engineering Co., Ltd.), and R. W. Vawdrey (Indented Bar & Concrete Engineering Co., Ltd.).

Associates: Messrs. P. G. Bowie, S. Champion, Ph.D., M.Sc., F. C. Eales, J. R. Liversedge, D. H. New, J. North, and F. S. Snow.

Branch Delegate: F. L. Abel (Richard Abel & Sons, Ltd.).

Past Presidents: Messrs. J. Cuerel, E. Wingrove Keer, A. R. Neelands, M.C., J. Singleton-Green, M.Sc.

Foundation for a Turntable.

THE illustrations show a prestressed concrete foundation recently built at Wath-on-Deerne in connection with the electrification of the Manchester-Sheffield-Wath railway. Prestressed concrete was used because the site is liable to mining subsidence, and settlements up to 4 ft. have taken place nearby. The design was produced in the department of the Civil Engineer of the Eastern Region of British Railways.

The foundation is in the form of a circular rim of 70 ft. diameter with four main radial beams and four secondary radial beams. The rim is 3 ft. 6 in. high by 2 ft. wide. The radial beams are

3 ft. 6 in. high by 1 ft. 6 in. wide. The prestressing wires for the rim are in two chases on the outside of the rim; there are two cables each of 24 wires in each chase. In the radial beams there is a cable comprising 64 wires near the top and a cable of 56 wires near the bottom. The rim and the radial beams are designed to act either as beams or cantilevers, so that in the event of local settlement the foundation will be capable of carrying an engine without breaking and be restored to its former level by jacks. The anchorages for the wires are provided by Magnel-Blaton plates. Mr. C. R. Price was the contractor.




Fig. 1.—Foundation During Construction.



Fig. 2.—Tensioning the Cables in a Radial Beam.

Concrete Piles in Holland.

By P. F. van der MEULEN BOSMA.

DUE to the nature of the soil, large numbers of piles are used in the Netherlands. When they are made on the site the piles are generally cast on thin concrete bases. To economise in moulds and space the following practice is commonly used: First piles Nos. 1, 3, 5, etc., of a layer are made and are exactly spaced to permit other piles to be made between them. When the moulds are taken away, the piles already made are covered with paper or coated with clay and piles Nos. 2, 4, 6, etc., are cast between them. This procedure is repeated for succeeding layers. Concrete piles up to 80 ft. long with a diameter of 16 in. and weighing up to $8\frac{1}{2}$ tons are made in factories by the centrifugal process. Generally, however, factory-made piles are seldom longer than 30 ft. due to the difficulty of transport.

Enlarged Points.

In addition to normal types of points, a point with an enlarged cross section (*Figs. 1 and 2*) and a patented "wing" point (*Fig. 3*) are used in soils where frictional resistance is practically nil but under which a stiff layer is found. The points shown in *Figs. 1 and 2* are similar to the points of large piles, but to save weight and material the enlarged section ends above the point and is replaced by a smaller cross section; for example, if the enlarged section is 16 in. square the upper part of the pile is 12 in. square. The increase of the load-carrying capacity of the point is then about 80 per cent. The "wing" point, due to its larger contact area with the soil, can carry a load about 50 per cent. greater than a normal point.

Piles with normal points are often made without pallets on an oiled concrete base. Piles with special points are made on pallets. The moulds are in most cases fixed with joiner's cramps. In some cases the longitudinal bars are bent over just under the top, so the ends of the bars can be exposed easily when the piles are driven.

The city of Rotterdam has patented a special method of casting piles with enlarged points (*Fig. 4*). The area of the cross section of the point is twice the area of the remainder of the pile. Piles No. 1 are first cast. After removal of the

moulds, piles No. 2 are cast between piles No. 1. This system is very economical in the use of moulds and space. The piles are marked with painted bands before they are moved; black bands indicate the places where the piles are to be supported when they are lifted horizontally, stacked, or transported, and red



Fig. 1.




Fig. 2. Fig. 3.




Fig. 4.

bands show the places where the piles are to be supported when they are lifted for driving.

Piles in Two Parts.

A patented pile, known as the "Duplex," is shown in *Figs. 5 and 6*. These are made in total lengths up to 70 ft. with diameters of 10 in. and 12 in. The parts are made in maximum lengths of 35 ft. The top of the lower part has a circular section 1 ft. 4 in. long. The lower end of the upper part has an enlarged section 1 ft. 4 in. long which is lined with four oak guide-strips. When the lower part is partly driven mortar is placed on the top of it, so that when the upper part is placed on it and driven the mortar is pressed into the joint; a ring of rope, placed in a groove around the lower edge of the upper part, prevents loss of mortar. The advantages of this type of pile are that the shorter pieces are easier to transport, lift, and drive, and that a shorter and lighter pile-driver can be used. The joint is claimed to be as strong as a normal section.

Sheet Piles.

Sheet piles are extensively used in the Netherlands. Generally these are the common type with V or tongue-and-groove joints.

Sheet piles with semi-circular grooves in the sides (*Fig. 7*) are used to line canals in soils containing much fine sand. They are placed with a water-jet so that a battered end is not needed. A steel pipe or bar, of about $1\frac{1}{2}$ in. outside diameter, is first driven and the first pile is placed with a jet so that one groove fits against the bar. In the other groove a second bar is placed, and this is followed by further piles with bars between them. The bars are pulled out as soon as possible, and are replaced immediately by a dry creosoted wooden stick of slightly smaller diameter. When the stick becomes wet it fills the space completely and so prevents leakage of fine sand. The upper part of the stick decays in ten years, but by then the cores are filled with roots of grass and moss. The lengths of the piles are limited by the lengths of the sticks and generally only two sizes are made, namely, 3 in. by 1 ft. 8 in. by 9 ft. 10 in. and 4 in. by 1 ft. 8 in. by 13 ft. $1\frac{1}{2}$ in.

Due to the mass production of these types, special reinforcement cages have




Fig. 5.



Fig. 6.




Fig. 7.




Fig. 8.




Fig. 9.—Reinforcement Crimping Machine.

been developed which give economy in steel and labour. The $\frac{1}{4}$ -in. links are crimped (Fig. 8) several at a time in a special press. The machine used for crimping the wires is shown diagrammatically in Fig. 9. The handle turns an eccentric wheel (which is greased) which forces the lever (a) to the lower position. The bars to be bent (b) are placed on the rolls (c), which are round steel bars or pipes. Similar rolls (d) on the lever are staggered between the rolls (c) so that when the lever is pushed down the wires are crimped as shown by dotted lines. A helical spring is used to keep the handle in the raised position while the crimped bars are removed and more straight bars are placed in the machine.

The links are electrically welded to the longitudinal bars, and circular bar-spacers are added. The bars are welded to the apexes of the bends in the links. Reinforcement for the shorter piles comprises eight $\frac{1}{2}$ -in. bars and thirteen $\frac{1}{4}$ -in. links. For the longer piles the reinforcement is eight $\frac{3}{4}$ -in. bars and seventeen $\frac{1}{4}$ -in. links. The piles are slightly tapered, eliminating the need for special wedge-shape piles. At a distance of 6 in. from both ends $1\frac{1}{2}$ -in. holes are formed to facilitate lifting and placing; these holes are later filled with mortar.

Fig. 10 shows a small bridge with abutments formed of tongue-and-groove sheet piling with special corner posts. This type of bridge can be built without interruption to the flow of the water and is often used in wet areas.

July, 1952.



Fig. 10.




Fig. 11.

Most specifications require the concrete for sheet piles to have a compressive strength of 5000 lb. or 6500 lb. per square inch on test cubes. Much higher compressive strengths are obtained in many cases, sometimes up to 12,000 lb. or 13,000 lb. per square inch.

Anchors for Sheet Piles.

Anchors for sheet-piled walls are generally of the shape shown in Fig. 11. The slabs have one, or sometimes two, meshes of $\frac{3}{8}$ -in. bars at 4 in. to 6 in. centres. The

anchor-bars are $1\frac{1}{2}$ in. or 2 in. diameter and are connected to cast-in-situ beams or copings on top of the sheet piles. The steel is covered with bituminous paint or other protection. The tops of sheet piles which are to be driven with a hammer have a small projection with a curved top to form a shoulder to receive a well-fitting rope and wooden cushion.

Extensions for Wooden Piles.

Figs. 12 to 15 show a type of concrete pile, known as "oplangers," which are used to extend and to continue the driving of wooden piles. These are of various patented types. Their advantages are :
(a) Long piles to carry light loads are cheaper in a wood-concrete combination




Fig. 16.




Fig. 17.

than in all-concrete construction; (b) the pile-driver can be lighter and shorter; (c) wood is less affected than Portland cement concrete by chemicals in the soil. The shapes of the bottoms of some types of these extensions are shown in *Figs. 12 to 15*, together with the shapes of the tops of the wooden piles. The shapes shown in *Figs. 12 and 15* are designed to lock the concrete and wood together. The concrete extension in *Fig. 12* is driven so that it locks on the tapered head of the wooden pile, while in *Fig. 15* the head of the pile is cylindrical so that the wood is slightly compressed when the extension is driven on it. When the ground water reaches the joint, the wood expands and fills the dovetail shape in the extension shown in *Fig. 15*. *Figs. 13 and 14* are similar designs; the wood is compressed in *Fig. 13* resulting in a slightly stronger joint, although this may stop the circulation

of water through the wood. To prevent the formation of an air-cushion in the joint, vents are provided as shown in the drawings.

These concrete extensions are hexagonal, octagonal, or circular in cross section. They are generally made in lengths of from 3 ft. to 12 ft., but sometimes up to 18 ft. Other common dimensions are given in the illustrations. The concrete extensions cannot be used for sloping piles. *Fig. 16* shows a concrete extension being placed on a wooden pile, and *Fig. 17* shows a foundation in which these composite piles are used.

The reinforcement is often welded and consists of eight or more bars of $\frac{3}{4}$ in. or $\frac{1}{2}$ in. diameter. The helical binding is in most cases $\frac{1}{4}$ in. in diameter and is very closely-spaced around the joint at the bottom, where there are often two helices of $\frac{3}{4}$ -in. or $\frac{1}{2}$ -in. bars.

Lecture Courses on Roads.

LECTURE courses will be held at the Road Research Laboratory, Harmondsworth, during the autumn and winter of 1952-53 on the properties of road materials and their application. The courses on concrete roads will be held on November 18 to November 27 and on December 2 to December 11. A fee of £10 10s. will be charged for each course. Forms of application can be obtained from the Director, Road Research Laboratory, Harmondsworth, Middlesex.

A two-days' course on the stabilisation of soil with cement has been arranged, in co-operation with the Cement and Concrete Association, on August 20 and 21 at the Association's Training Centre, Wexham Place, Stoke Poges, Bucks. (near Slough), from which particulars can be obtained (there will be no fee for this course).

Reinforced Concrete Louvres.

ONE of the walls of the new chemistry building at the University of Hongkong will consist entirely of movable reinforced concrete louvres, which can be raised and lowered (like a Venetian blind) when necessary to shield the rays of the sun.

Four Reinforced Concrete Chimneys at Fawley, Hants.

THE initial scheme for the new Esso refinery at Fawley, on Southampton Water, allowed for three reinforced concrete chimneys 250 ft. high above ground, and it was later decided to include a fourth chimney of the same height. One chimney serves the boiler plant, another the atmospheric heater, another the atmospheric and vacuum heaters, and the fourth (*Fig. 1*) also serves the boiler plant. The chimneys were constructed by Custodis (1922), Ltd., of London, the first three being designed by the Custodis Construction Company of New York and the fourth by Custodis (1922), Ltd., London, in each case in co-operation with Foster Wheeler, Ltd., who were the designers and engineers for the refinery.

The chimneys were designed in accordance with the American standards, which have been the basis of design for most of the very large chimneys in America for the past fifteen years, modified by the provisions of the British Standard Code of Practice, under which the design is based on a wind velocity of 78 miles per hour, and the building by-laws of the Rural District Council which require a wind load of 25-lb. per square foot to be assumed on the vertical projection for the full height. The possibility of earthquake was not considered. The main design data were: Weight of concrete, 150 lb. per cubic foot; weight of firebrick in place, 130 lb. per cubic foot; compressive strength of concrete at 28 days, 3750 lb. per square inch; atmospheric temperature, 20 deg. F.; maximum temperatures—boiler chimneys, 650 deg. F.; atmospheric heater chimney, 900 deg. F.; atmospheric and vacuum heater chimney, 1000 deg. F.

The chimneys taper from bottom to top. The thickness of the walls and the vertical reinforcement were designed to resist the dead load, the wind, and temperature effects, and the circumferential reinforcement was designed to resist diagonal tension and horizontal temperature effects.

The Shafts.

The diameter inside the lining is 8 ft. at the top and 11 ft. at the bottom in the




Fig. 1.

case of the first boiler chimney, and 9 ft. and 12 ft. respectively in the case of the other three chimneys. In all the chimneys the lining is $4\frac{1}{2}$ in. thick at the top and 18 in. thick at the bottom; there is a minimum air-space of $4\frac{1}{2}$ in. between the shaft and the lining. In all cases the concrete is 6 in. thick at the top, increasing to 12 in., 13 in., or 14 in. at the bottom.

The reinforcement of the first boiler chimney comprises 32 vertical $\frac{1}{2}$ -in. bars at the top increasing to 124 $\frac{1}{4}$ -in. bars at the bottom, and $\frac{1}{2}$ -in. bars at 12-in. centres circumferentially. The second boiler chimney has 34 vertical $\frac{3}{8}$ -in. bars at the top increasing to 140 $\frac{3}{4}$ -in. bars at the bottom and circumferential reinforcement of $\frac{3}{8}$ -in. bars at 12-in. centres. The other two chimneys have 34 vertical $\frac{1}{2}$ -in. bars at the top increasing to 164 $\frac{3}{4}$ -in. bars at the bottom and $\frac{1}{2}$ -in. circumferential reinforcement at 12-in. centres in the case of the chimney for the atmospheric heater and at 10-in. centres in the chimney for the atmospheric and vacuum heaters. There is additional vertical, diagonal, and circumferential reinforcement at flue openings, of which there are two in each of the boiler chimneys and vacuum-heater chimney, and one in the atmospheric-heater chimney. The total amounts of reinforcement and concrete in the shafts are respectively 15.1 tons and 259 cu. yd. in the first boiler chimney, 16.5 tons and 284 cu. yd. in the atmospheric-heater chimney, 17.6 tons and 282 cu. yd. in the vacuum-heater chimney, and 18.75 tons and 307 cu. yd. in the second boiler chimney.

Foundations.

The foundations of all the chimneys are designed for an earth pressure of 2 tons per square foot at 7 ft. below ground level, where bores indicated a stratum of fine silica sand. In the case of the first boiler chimney pockets of clay were encountered and another 10 ft. were excavated, the additional excavation being filled with mass concrete on which the foundation was constructed. All the foundations are octagonal in plan and reinforced top and bottom with vertical bars tied to the reinforcement in the shafts.

The total weight on each foundation is about 1000 tons, and the sizes of the foundations are 38 ft. wide by 8 ft. thick (excluding the sub-base of the shaft) for

the first boiler chimney and 39 ft. 6 in. wide and 7 ft. 6 in. thick for each of the other three chimneys. The amount of reinforcement in the foundations is about 17½ tons for the first boiler chimney, 12½ tons for the second boiler chimney, and 10½ tons for each of the other two chimneys.

Lining.

A lining of Glenboig (for three) and Craigend (for one) fire-bricks set in fire-clay was used, except for the top 35 ft. which was constructed entirely of American acid-proof bricks laid in acid-resisting putty. The upper 6 ft. 6 in. of the shaft of each chimney was constructed entirely of acid-resisting bricks 9 in. thick, because the acid resulting from the combination of the oxides of sulphur with atmospheric or condensed moisture under adverse weather or temperature conditions is liable to cause damage to concrete and firebrick. The linings are reinforced with 3-in. by $\frac{1}{4}$ -in. bands spaced at different intervals in the case of the chimneys serving the boilers and those serving the atmospheric heater and atmospheric and vacuum heaters, and in the former case the bands are covered with sheet lead. In the case of the chimneys for the atmospheric heater and the vacuum heater the bands in the upper 35 ft. are of stainless steel. The steel channels which bridge the bands at the flue openings in the boiler chimneys are covered with lead; in the other chimneys these channels are of light steel alloy. The openings to permit circulation of air in the annular space between the lining and the shaft are at the bottom of the outer shafts and at a height of 150 ft. in each chimney, the top of the annular space being left open to the atmosphere.

Fittings.

At the top of each chimney cast-iron caps $\frac{3}{4}$ in. thick cover the lining and the outer shaft. The sections of the caps are bolted together with stainless-steel bolts. The cap is designed to permit differential expansion of the lining and the shaft.

Access to the top of each chimney is by $\frac{7}{8}$ in. diameter galvanised step-irons 15 in. wide spaced at 12 in. centres vertically. Access to the inside of the chimneys is through 24-in. by 36-in. cast-iron clean-out doors. A curtain wall is provided in the linings to protect the doors from gases.

The lightning conductors comprise six $\frac{5}{8}$ -in. diameter monel-metal vertical projection rods and two 1-in. by $\frac{3}{8}$ -in. copper-tape conductors on opposite sides of each chimney, the upper 25 ft. of the tapes being covered with $\frac{1}{16}$ -in. lead.

Four lights are installed at 150 ft. above ground and four at 240 ft. above ground as warnings to aircraft; access to the lights is by step-irons.

Construction.

The shaft of the first chimney was commenced on May 24, the second on July 19, and the third on September 7, 1950.

The shafts were completed on August 25, October 24, and December 2, 1950, respectively. Immediately following completion of the shafts the brick tops were constructed, and the firebrick lining of the first chimney was commenced on March 25, the second on April 29, and the third on May 5, 1951. The first chimney was completed on April 29, the second on June 14, and the third on June 28, 1951, about four months ahead of the schedule. The last chimney was commenced in July, 1951; the shell was completed early in October, and the lining was completed by the middle of December.

Prestressed Concrete Sheet Piles.

PRESTRESSED concrete sheet piles were used at the new iron ore quay at Tyne Dock to form a curtain wall. The piles are 40 ft. long and $23\frac{3}{4}$ in. by 9 in. in cross section. The tongues and grooves on the sides are designed to permit the introduction of colloidal grout between the piles after driving. There are 84 0.2-in. diameter high-tensile steel wires in each pile; in addition, mild steel is provided in the head and toe and stirrups are provided throughout the length of the pile. The head is slightly reduced in cross section, and the toe is pointed and bevelled so that each pile is forced against its neighbour during driving. No shoes are fitted. The piles were manufactured at the Tallington works of Messrs. Dow-Mac (Products), Ltd. Each pile (*Fig. 1*) weighs approximately 4 tons, and the lifting points were marked before despatch.

The driving was done by the main contractors, the Yorkshire Henebique Contracting Co., Ltd., with a 3-tons single-acting hammer with a drop of 4 ft. Bolt-holes in the piles were not permitted, and the piles were held in the leaders by means of clamps. Hard driving conditions were experienced, and up to 150 blows per foot of penetration were required in many cases; the damage to the heads of the piles was, however, negligible. The piles were designed by Mr. R. B. Porter, M.I.C.E., chief engineer of the Tyne Improvement Commission;



Fig. 1.—Lifting a Pile.


the consulting engineers were Messrs. Rendel, Palmer & Tritton.

Pressure-Type Air Meters for Air-Entrained Concrete.*

BY P. J. F. WRIGHT, B.Sc., and A. D. McCUBBIN

OF THE ROAD RESEARCH LABORATORY, DEPARTMENT OF SCIENTIFIC AND INDUSTRIAL RESEARCH.

THIS article describes tests carried out at the Road Research Laboratory on three pressure-type "air meters" for measuring the air content of air-entrained concrete. In these meters a known pressure is applied to a given volume of freshly-mixed concrete and the resultant decrease in volume of the concrete is



(a) Before applying pressure

(b) With pressure applied

Fig. 1.—Diagram of Pressure-type Apparatus for Determining the Air Content of Air-entrained Concrete.

measured. The method has been fully described elsewhere^{(1) (2)} and is illustrated diagrammatically in Fig. 1. The air content indicated by each meter was compared with the air content obtained by a gravimetric method.^{(2) (3)}


The principal purpose of entraining air in concrete is to improve its resistance to frost. The workability is also improved, but this is accompanied by a reduction in compressive strength which, if the water-cement ratio is constant, amounts to about $5\frac{1}{2}$ per cent. for each 1 per cent. by volume of air. If, however, the water-cement ratio is reduced so that the workability remains constant, and other minor modifications are made to the proportions of the concrete, air may

* Published by permission of the Director of Road Research.

be entrained with little or no loss of strength. The amount of air entrained varies with different cements, proportions, and aggregates, and with the temperature, and it must be controlled within limits (frequently 4 per cent. to 6 per cent. by volume); if the air content is too high the strength will be seriously reduced, while if it is too low the workability will be reduced. Thus a simple and reliable instrument is desirable for measuring the air content at regular intervals, and the pressure-type meter has found favour in America. An instrument of this type has recently been made at the Road Research Laboratory,



No. 1.



No. 2.



No. 3.

Fig. 2.—Types of Air Meters.

and before it was put into general use its performance was compared with that of other available pressure-type air meters and with the gravimetric method previously used.

Details of the Air Meters.

The air meters used were as follows. (1) A proprietary air meter, with a capacity of about $\frac{1}{4}$ cu. ft. of concrete, designed to measure from 0 to 7.5 per cent. of air. This instrument was received already calibrated in percentage air content when operating at a pressure of 15 lb. per square inch. (2) An air meter made at the Building Research Station, with a capacity of about $\frac{1}{4}$ cu. ft., designed to measure up to 8 per cent. of air. (3) An air meter made at the Road Research Laboratory, with a capacity of about $\frac{1}{10}$ cu. ft., designed to measure up to 9 per cent. of air. Meters (2) and (3) were calibrated at the Laboratory at an operating pressure of 15 lb. per square inch. The more common method is to use a pressure such that the graduated scale indicates the air-content directly, but for these

tests a pressure of 15 lb. per square inch was used for all the meters. The three air meters are illustrated in *Fig. 2*.

Scope of Tests.

One mixture was used in the proportions of 1 : 7½ by weight of dry materials, using normal Portland cement, graded river gravel aggregate of ¾ in. maximum size, and river sand, the sand comprising one-third of the total aggregate. In order to produce a mixture suitable for hand compaction a water-cement ratio of 0.67 was used; from preliminary tests this was found to give a compacting factor of 0.95 when about 5 per cent. of air was entrained.

Vinsol-resin was used to entrain the air, a 10 per cent. pre-neutralized solution in sodium hydroxide being added to the mixing water just before mixing. The quantity of solution was such that the weight of Vinsol-resin was 0.015 per cent. of the weight of cement, and this entrained an average of about 6 per cent. of air. The concrete was mixed in an open-pan paddle-type mixer of 1 cu. ft. capacity; twelve batches were made and on each batch four determinations of the air content were made, three by the air meters and one by the gravimetric method. Two operators carried out the tests and each made two of the determinations on each batch. The operators changed instruments after each batch. Two additional batches were made in the same proportions but with the quantity of Vinsol-resin reduced to give about 2 per cent. of entrained air; tests were made on these mixtures with two of the air meters and by the gravimetric method.

Methods of Determining the Air Content.

GRAVIMETRIC METHOD.—The vessel used was the cylinder of a compacting-factor apparatus, which has a volume of about ½ cu. ft. The concrete was compacted by hand in 2-in. layers with 25 blows of a standard 4-lb. punner. The cylinder was filled level and screeded off. It was then weighed to the nearest 5 gm. and the air content was found by comparing the weight of air-entrained concrete with the theoretical weight of the same volume of concrete free from air, calculated from the known proportions and densities of the constituents.

PRESSURE METHOD.—For each instrument the concrete was compacted as for the gravimetric method, the number of blows of the punner being proportional to the volume, assuming that 150 blows were appropriate for a volume of ½ cu. ft. When the vessel was full and screeded off, a thin circular metal plate was placed on top of the concrete to prevent the water eroding the surface of the concrete, the top section was clamped down tight and filled with water to the top mark on the scale. Air pressure was applied with a bicycle pump up to 16 lb. per square inch; the pressure was then found to drop slowly (probably due to the porosity of the aggregate), and when the pressure gauge recorded 15 lb. per square inch the water level was read to the nearest 0.1 per cent. of air content. The air pressure was then released. The water level did not fully return to zero owing to the effect of the porosity of the aggregate; the small correction was noted and subtracted from the gross air content.

Results of Tests.

The results of the tests are given in *Table I*. The average air contents of the batches varied considerably; larger variations might be expected on a con-

structional site if no effort were made to control the air content. The agreement between different instruments was good, and a statistical analysis of the results showed that there was no general difference between the values obtained with different instruments, although No. 4 gave higher values than No. 1. The difference here may have been due to a calibration error in No. 1 or to a real difference between the gravimetric and pressure methods. This suggests that it would be

TABLE I.—RESULTS OF MEASUREMENTS OF ENTRAINED AIR.
(Figures are percentages of air by volume.)

Meter	1 (Proprietary)	2 (B.R.S.)	3 (R.R.L.)	4 (Grav.)	Average
Batch 1	3.5	3.6	3.6	3.5	3.55
2	5.8	5.4	5.8	5.8	5.7
3	6.1	6.7	6.7	7.1	6.65
4	6.6	7.2	6.4	7.8	7.0
5	5.6	5.3	5.7	5.7	5.6
6	5.6	5.8	5.5	5.7	5.65
7	6.7	6.2	6.5	6.7	6.5
8	6.5	6.4	6.7	6.7	6.6
9	5.3	6.1	5.5	6.2	5.8
10	5.3	5.3	5.6	5.6	5.45
11	5.2	5.9	5.8	6.1	5.75
12	5.4	6.3	6.4	5.9	6.0
Average	5.6	5.85	5.85	6.1	5.85
Standard deviation within batches .	0.28	0.23	0.25	0.25	
13	1.5	—	1.7	1.7	1.63
14	1.4	—	1.5	1.8	1.57


advisable to check the calibration of any instrument before use. The analysis did not show any difference in the uniformity of results obtained with different instruments.

The time taken to carry out the tests was about five minutes for each determination. The gravimetric determination was the quickest since the time required to weigh the vessel was less than that required to complete the pressure operation; however, the calculation of the gravimetric result takes longer, additional apparatus (a balance) is required, and accurate information regarding proportions and specific gravity is needed. Meter No. 3 was the quickest to use of the pressure meters, owing to the relatively small volume of the concrete and to the ease of filling the instrument with water. The test with meter No. 1 took longest, mainly owing to the presence of a plate perforated with small holes in the filling funnel which increased the time required to fill the meter with water. The plate was intended to prevent stones entering the meter and becoming lodged in the gauge-tube, but this might have been achieved more satisfactorily by using gauze and a larger hole or holes. The hinged clamping screws of meters Nos. 1 and 3 were preferred to the loose G-clamps of meter No. 2 for fastening down the top section. Meter No. 2 had been designed with G-clamps so that the

STEEL FORMS



The well-known Multiple system of STEEL SHUT-
TERING for IN-SITU cast concrete construction



A. A. BYRD & CO., LIMITED


210, Terminal House,

Grosvenor Gardens, London, S.W.1.

'Phone: SLOane 5236.

'Grams: Byrdicom, Wesphone, London.

for all types of



SHUTTERING...

**tubular scaffolding &
builders plant
contract or hire**

- try SGB

SCAFFOLDING (GREAT BRITAIN) LTD
MITCHAM SURREY

Telephone: MITCHAM 3400 (18 lines) Telegrams: SCAFCO, MITCHAM

Depots & Branches in all Principal Towns & Cities, Ireland & South Africa



- the originators of tubular scaffolding!

cylinder could be used more easily for determinations of density and similar purposes.

Conclusions.


It was found that, under the test conditions, the pressure and gravimetric methods both gave reliable results. For site conditions the pressure method is preferred, as it does not require an accurate balance, is simple to use, and provides a direct reading; also it does not require an accurate knowledge of the proportions of the concrete, which is normally lacking on the site owing to inevitable variations. The $\frac{1}{10}$ cu. ft. cylinder of meter No. 3 was satisfactory with $\frac{3}{4}$ -in. maximum size aggregate.

REFERENCES.

- (1) Menzel, C. A. Procedure for determining the air content of freshly mixed concrete by the rolling and pressure methods. *Proc. Am. S.T.M.*, 1947, 47, 833.
- (2) Klein, A., Pirtz, D., and Schweizer, C. B. Comparison of three methods of measuring air-entrainment in concrete. *Proc. Am. S.T.M.*, 1947, 47, 876.
- (3) American Society for Testing Materials. Standard method for test for weight per cubic foot and air content (gravimetric) of concrete. Am. S.T.M. Designation C138-44. A.S.T.M. Standards, 1944. Part II. Non-metallic materials—constructional, pp. 487-9. Philadelphia, Pa. 1944 (Am. S.T.M.).

High-pressure Production of Concrete BLOCKS

TRIANCO
Nº K'2 Type
BLOCK MAKING MACHINE
Power Operated
Fully Automatic



This machine is specifically designed for the mass production of SOLID BLOCKS and is capable of producing 300 blocks per hour, which are jolted, compressed and extruded automatically. Fitments are also available for the manufacture of hollow blocks.

DELIVERY FROM STOCK

Full specification will be sent on application

TRIANCO LIMITED
IMBER COURT, EAST MOLESEY, SURREY
Telephone: EMBerbrook 3300

TRIANCO
BLOCK-MAKING MACHINES

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 3d. a word: minimum 7s. 6d. Situations Vacant, 4d. a word: minimum 10s. Other miscellaneous advertisements, 4d. a word: 10s. minimum. Box number 1s. extra. The engagement of persons answering these advertisements is subject to the Notification of Vacancies Order, 1952.

Advertisements must reach this office by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Reinforced concrete designer-drafters. Two vacancies. Salaries between £650 and £750 p.a. according to experience. Applications to W. V. ZINN, Coastal Chambers, Buckingham Palace Road, London, S.W.1.

SITUATION VACANT. Progressive Midlands firm requires senior reinforced concrete designer. House may be supplied to suitable applicant. Pension scheme in operation. Box 2567, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Experienced reinforced concrete designers and drafters required for foundations and superstructures of chemical plant and oil refineries. Also vacancies for younger men wanting experience of large projects. Salary according to capabilities. Generous pension scheme, and free life insurance. Write CHIEF ENGINEER, E. B. BADGER & SONS (G.B.), LTD., 40 Parkgate Road, London, S.W.11.

SITUATIONS VACANT. Two draughtsmen required. (1) With experience of general building design, and knowledge of cast stone; (2) One who, in addition to working on board, is willing to train in production control, and to carry out experimental work on new products, including prestressed concrete. The latter post ideal for young man studying for his National or Higher National Certificate, and offers excellent promotion prospects for right type. Reply to DESIGN DEPARTMENT, STENT PRECAST CONCRETE, LTD., Chequers Lane, Dagenham.

SITUATION VACANT. Peter Lind & Co., Ltd., civil engineering contractors and reinforced concrete specialists, of Stratton House, Piccadilly, London, W.1, require a qualified civil engineer for their projects and estimating department. Apply in writing only, stating age, experience, and salary required.

SITUATION VACANT. Wanted. Junior designer-draughtsman for precast and prestressed concrete work. Age 22-25. Applicants must have some experience in reinforced concrete design and sufficient technical knowledge to acquire prestressed concrete design quickly. Preference will be given to a man with previous training in mechanical office. Salary according to age and experience. Apply CHIEF DESIGNER, DOW MAC (PRODUCTS), LTD., Tallington, near Stamford, Lincolnshire.

SITUATION VACANT. Chief designer required by consulting structural engineers, Westminster. Considerable experience of reinforced concrete buildings essential, and experience of structural steelwork desirable. Applications in confidence, stating age and qualifications, with full details of experience. Box 2536, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. The British Reinforced Concrete Engineering Co. Ltd. require several qualified designers with specialist experience for their Stafford, London, Bristol, Glasgow, and Newcastle-upon-Tyne offices. Five-day week, and staff pension scheme. Apply to B.R.C. ENGINEERING CO., LTD., Stafford.

SITUATIONS VACANT. The Trussed Concrete Steel Co. Ltd., Truscon House, 35-41 Lower Marsh, London, S.E.1, require additional staff in their London and Manchester design offices: (a) Designer-Detailers (age 25 or over), (b) Detailer-Draughtsmen (age 20 or over). Previous good experience in reinforced concrete drawing office is important. Five-day week and pension scheme. Apply in writing to the above address giving full particulars of age, education, and previous employment.

SITUATION VACANT. Experienced designer (senior) required for Nairobi, Kenya, by long-established company of reinforced concrete specialists employed primarily on design of commercial structures. 4½-years' contract (renewable) with paid passage. Home leave and pension schemes. Write Box JU/123, 95 Bishopsgate, London, E.C.2.

SITUATION VACANT. Senior executive required by a Liverpool precast concrete manufacturer. Previous knowledge of concrete manufacture an advantage, but administrative ability and experience a necessity. Four-figure salary according to qualifications, with pension scheme. Box 2569, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete designer and several detailer-draughtsmen required. Excellent prospects. Five-days' week. Pension scheme. C. J. PELL & PARTNERS, CONSULTING ENGINEERS, 4 Manchester Square, London, W.1.

SITUATIONS WANTED.


SITUATION WANTED. Young Norwegian seeks employment in Great Britain. Civil engineering degree from the Technical University of Denmark. One year's experience in office of structural engineering consultant. Particularly interested in reinforced concrete. Write to EINAR FURRE, c/o Agersborg, Bogstadvæien 11, Oslo, Norway.

SITUATION WANTED. Final year Higher National student desires position on outside staff in London area to qualify for Section C of A.M.I.C.E. Married, national service completed, and six years' experience as detailer-draughtsman with reinforced concrete contractors. Box 2578, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR SALE.

FOR SALE. Steel-angle fencing stakes, 54 in. by 1½ in. by 1½ in. by 14-gauge. Holes at 6-in. intervals; pointed and painted, at 2s. each, 50 lots; 1s. 11d. each, 100 lots; 2s. 6d. each, 1,000 lots; carriage paid. Other sizes available on request. E. STEPHENS & SON, LTD., 58/64 Bath Street, London, E.C.1.

REINFORCEMENT: 350 tons barbed wire, concertina type, in 40-lb. coils, at £21 per ton; 10 tons mixed round hexagons at £32 10s. per ton. **STEEL PLATES:** 10 tons ½ in. to 1 in. plates, sizes 2 ft. x 9 in. to 15 ft. x 24 in., at £30 per ton. **STEEL SHEETS:** 20 tons ½ in. painted, non-bending quality, minimum size 3 ft. x 2 ft., at £32 10s. per ton. **STEEL ANGLES:** 25 tons 5 in. x 5 in. x ½ in. x 18 ft. long at £26 per ton. **SHEARED STEEL STRIPS & PLATES:** Supplied in all widths and gauges. **FABRICATION & PRESSWORK** of all kinds; special angles, channels, gutters, etc. E. STEPHENS & SON, LTD., 58/64, Bath Street, London, E.C.1.





ALPHA CEMENT LTD


PORTLAND HOUSE, TOTHILL STREET

LONDON, S.W.1.

Telephone - Abbey 3456.

FRED MITCHELL & SON LIMITED

Building & Civil Engineering Contractors



*Bridge, Road and Rail Construction,
Cooling Towers, Silos & Commercial Buildings,
Excavations, Foundations, Piling,
Dock and Sea Defence Work,
Water Mains, Sewerage, Reservoirs etc.*

RIVER PLACE · CITY ROAD · MANCHESTER

Telephone: Central 7018-9